DRAGON USER

The independent Dragon magazine

December 1986

Contents

Editorial

FAIR, fat and forty pages this month The Dragon trading nation has been saving up its pennies for Christmas with the result that our advertisers are back in force this month I hope you lot have been saving your pennies for an extra game or two to make their effort worthwhile So you get tired of a game in the end? So donate it to Mr Orbaum With disc drives like his he needs something he can play on tape —

The Royal Horticultural Halls in London Mecca of the minor micro (as I write, the Electron users are gathering for their annual show) is host to Microdeal and the 6809 Show on 22 November Be grateful that I have a prior engagement in York or you could find me there with a tray of backissues Dragons Dragons lovely Dragons get your Dragons here

I have half a dozen July 86 issues here in the office £1 25 each, first come, first serve We may subsequently have news on where you can get good copies of this rarity Sorry I can't tell you where they came from — nobody seems to know The tooth fairy?

One of our good suppliers may not be back in the Dragon market next year See if you can spot which one and send em a Christmas card because they've done well by the old machine And a happy Christmas to you all if I don't see you till after the hols—

Telephone number
(All departments)
437 4343

Editor
HELEN ARMSTRONG

Production Editor
BARBORA HÁJEK

Associate Editor
JOHN COOK

Editorial Secretary
ANNE MARIE O DWYER

Advertisement Manager
RODNEY WOODLEY

Administration
GERALDINE SMYTH

Marketing Managar
Helen Perry

Managing Editor
PETER WORLOCK

Publishing Director
JENNY IRELAND

Subscriptions
UK £14 for 12 issues
Overseas (surface) £20 for 12 issues
ISSN 0265-177 Telex 299275
Dragon User 12/13 Little Newport Street London WC2H 7PP
US address c/o Business Press International 205 East 42nd St New York NY 10017
Published by Scot Press Ltd
Scot Press 1986
Typesetting and Production by Artext Limited London NW1
Printed by Headley Brothers Ltd Ashford Kent
Registered at the Post Office as a newspaper
Dragon and its logo are trademarks of Eurohard Ltd

How to submit articles

The quality of the material we can publish in *Dragon User* each month will to a very great extent depend on the quality of the discoveries that you can make with your Dragon The Dragon computer was launched on to the market with a powerful version of Basic but with very poor documentation

Articles which are submitted to *Dragon User* for publication should not be more than 3000 words long All submissions should be typed Please leave wide margins and a double space between each line Programs should whenever possible be computer printed on plain white paper and be accompanied by a tape of the program

We cannot guarantee to return every submitted article or program so please keep a copy If you want to have your program returned you must include a stamped addressed envelope

Letters

This is the chance to air your views — send your tips, compliments and complaints to Letters Page, *Dragon User*, 12-13 Little Newport Street, London WC2H 7PP.

Computer program

I ACCIDENTALLY discovered that it is possible to tune in an ordinary VHF radio and hear the Dragon processing. If you place the radio tuned in to any space between broadcasting stations and run a program you will hear definite signals. Loading, entering, processing data, displaying the results and waiting for an input all produce different sounds. I wonder if it would be possible to fit an antenna to the coaxial socket to improve the broadcast?

Paul Scott
15 Ryde Court
St Thomas St
Ryde
IOW

PS Why do advertisers postage and packing rates vary so much? How can one company justify £2 for posting a cartridge when another charges 75p or 50p or nothing at all?

COULD BE handy if you re making coffee in the kitchen Paul. But are you sure you weren't just picking up one of Tommy Vance s late nighters?

P&P charges often incorporate other overheads associated with running a mail order service, which is why big companies sometimes seem to make disproportionate charges for small packages. That, and the well known toss a coin method!

Win and load

MAY I raise my voice in support of Mr O Malloy in his request for the solutions of the competitions to be published. I frequently attempt the competitions but often fail to reach a conclusion. It would be interesting to know the methods which the winners use. As for what should be left out, well I have never seen the use of charts so I would not be sorry to see the Peoples Chart go.

Another way of saving space lies in the area of machine code programs. Every machine code program is accompanied by a loader program. Regular readers (and we must all be regular readers now) must have umpteen such programs or at least the ability to write their own so why not drop them? Alternatively print one program that can be adapted to different line lengths and give notice that no more will be published.

D Bateman
14 Hawthorn Way
Royston
Herts SG8 7JP

WELL, we re working on it — it's now partly down to Gordon Lee, a hard working chappie like most of us, finding the time to write a bit more for us each month. However as the winners are judged on their elegance it won't always be the winning few who get the guvnor s scrutiny - as much can be learned from looking at the less well turned programs as from the best ones.

Secondly it s a fundamental of all technical publishing below professional level that articles are self contained. You wouldn t believe the number of letters we get from people looking for a loader program of one sort or another. Don t be tempted, Mr Bateman!

Tape head tales

COMPLIMENT October edition is best one yet.

Suggestions box: hopefully most Dragon users with cassette based media no longer suffer the dreaded I/O Error syndrome, but for those who do, try adjusting the head azimuth of the tape recorder. Shock horror! Yes it is safe to do. Use the Audio On and Motor On commands to listen to the tape through the TV/Audio output and using a jeweller s screwdriver adjust the azimuth by turning the screw located behind the Play head. This is normally accessible through a tiny hole in the top case. After adjusting the head for maximum volume and sharpness of sound, the tape should load OK. If your other tapes then refuse to load, simply repeat the process using one of your previously saved program tapes.

Questions: anyone tried the Rainbow mod to get switchable normal/inverse video on the CoCo to see if it works on the Dragon? Anyone got a non working DOS cartridge for sale? Or a cheap working one? (Need it to house own DOS.)

Warning: I have a Sanyo DR101 data recorder out of guarantee well used expensive — it now erases every tape I try to load with it. When the problem started happening (only occasionally at first) I thought it was my Prognosis terminal caused by wear in the plastic erase head guides (b n it).

Paul Read
7 Fairview Avenue
Whetstone
Leicester LE8 3JQ

WHOA hold on just one moment: call Sanyo Marubeni on 0923 46363 before you bin your investment: ask for the Service department, and you will find that they can either sell you a replacement part (if you are able to fit it) or quote you for a repair. Let s be fair, you would wear out too if someone was dragging a length of iron-impregnated plastic across you for hours on end.

For postal enquiries, Sanyo's address is Otterspool Way, Watford, Herts WD2 8WD.

Magic puzzle

I RECENTLY found lurking on the local micro shop shelves a DragonDOS version of Sprite Magic. To my dismay it would not run with DragonDOS version 4. Investigating the problem I found that the word list and function list addresses and the addresses of word and function display tables were different from those expected by Sprite Magic.

Using a backup copy (prudent precaution in the event of a mistake) I found the following method overcame the problem:

```
CLEAR 200,&H6000
PROTECT OFF
SMCODE BIN
LOAD SMCODE BIN
POKE &H6EFD &HDA
POKE &H6F02 &HC1
POKE &H7685,&H6D
SAVE
SMCODE &H6E80,&H7FFF&
H6E80
```

I assume that CumanaDOS and SUPERDOS users will face the same problem but will require a different modification to the program.

David Gray
570 Acklam Road
Middlesborough
Cleveland TS5 8BE

Free pokes

I HAVE just finished compiling two A4 sheets containing pokes and cheats for Dragon games. They are designed as quick reference sheets so that you can easily find the poke you want without searching through your collection of Dragon Users looking for the right month. There are 55 games covered including The Dark Pit, Jet Set Willy, Menic Miner, Shock Trooper and many pokes which have never been printed.

If any DU readers would like copies of these sheets then I'll be happy to supply them if they send me a stamped self addressed envelope plus a 20p coin to cover the cost of photocopying.

Paul Burgin
18 Moorcroft Road
Sheffield S10 4GS

THANKS Paul. When sending coins through the post, tape 'em well down to the paper and wrap at least two sheets round them. Loose coins have a way of leaving envelopes en route.

Any CAD?

IT IS heartening to see that DU has been able to run four extra pages. I rely on the magazine to keep me up to date so while looking forward to its monthly appearance, I also look forward to its long term survival.

My children use the Dragon for games while I mostly use it for preparing technical papers, lectures etc. A very useful extension for me would be the ability to use it for draughting or Computer Aided Design. The problem here is that there no longer seem to be people rushing to produce CAD programs for the Dragon: could you consider an article which reviews the CAD software available for the D32 and D64?

M L Monaghan
18 Downsway
Shoreham-on-Sea
West Sussex BN4 5GN

Dragon User People's Chart

JINGLE BELLS! Jingle bells! The pantomime season must be here again because *Bean Stalker* from Micro Vision has clearly been applying some strong stuff to its roots and has shot up to the top slot. Look out for falling toilet rolls.

What about all this new stuff then? We were going to announce grandly that if all those hardworking software writers out there worked their fingers just a little nearer to the bone if the avalanche hit us in time for Christmas we should see some new names in the Chart. Well we can't speak can we? Four new reviews down the plug to oblivion. When Jason rang to say he'd had a crash we thought he must have fallen down the stairs but it was worse than that.

But at last! At last! We have the X factor! A bit of a narrow squeak to be sure but he's gone end done it. Mr Robin Hemmings of Wigston Leicester sends us this tie breaker. I Just need Part II! Alas it is not to be — but he should be getting some freebies soon.

Vote! Vote! Send in the form printed here or a copy with your five favourite progs and if you send us a knee-knotting tiebreaker made up from the letters (or some of em) of your own top three you could win £25 worth of games software from MICRODEAL.

Results November 1986

1 Bean Stalker.....(Micro Vision)
2 Juxtaposition.....(Wintersoft)
3 Shaolin Master.....(Quickbeam)
4 Shocktrooper.....(Microdeal)
5 Jet Set Willy.....(Software Projects)

Chart Ten

Voting for Chart No. 10 closes at 1pm on Friday 12th December 1986. Entries recieved after that time will not be eligible for inclusion in that month's voting. The editor's decision is final. Only one entry per individual per month will be allowed.

My top 5 Voting Month 10 — Name
1 — Address
2
3
4
5
My phrase is

News desk

If you have any new products for the Dragon — software or hardware — ring the News Desk on 01-437 4343

Analyzer corrections

The author of analyser has contacted us with corrections for two errors concerned with the row insert command

The altered lines to replace the lines with the correspondng numbers in the listings are as follows

```
12  POKES1T+O GOSUB1
RETURN
85  Z=VAL(MI$(T$(X)T+1 2))
IFK= GOSUB125 NEXT
RETURN
114 IFA$(M)=  ANDB$(M)=
ANDC$(M)=  ANDD$(M)=
NDE$(M)=  ANDF$(M)=
ANDG$(M)=  ANDH$(M)=
ANDI$(M)=  ANDJ$(M)=
THENM=M1 GOTO114
122  IFL(X)>-R  THENL(X)=
L(X)+1
123  NEXT FORX=70TOY IFM
(X)>R*Q THEN(X)=M(X)+Q
124 NEXT GOTO29
125 IFR>Z THENRETURNEL
SEMID$(T$(X)T+1 2)=RIGHT
$(STR$(Z+1) 2) RETURN
```

Monsters

Monster Alley is a multi screen arcade game which runs under (and only under) Sprite Magic Players are required to collect keys while avoiding monsters and a built in cheat mode accesses the next screen

The game costs £2 from K Hunt 11 Demarnham Close West Bromwich B70 6RI The first 25 orders will receive a free adventure with Sprite Magic is not on sale with the game

Apology

Quite inadvertently Dragon User The Expert and reader David Barclay combined to give the impression that the map of Juxtaposition on page 29 was Mr Barclay s own work The map was in fact orginally supplied by Wintersoft a point not made sufficiently clear by Mr Barclay who simply wanted to share his good fortune other readers In a letter to The Expert he says Please could you stress that I only sent it in for the readers and give the credit to Wintersoft as I don t want to get a bad name for myself Dragon User and Mr Barclay would like to apologise to all concerned for this misunderstanding

Incentive move

Incentive Software known to Dragon users for Moon Cresta have appointed an International Sales Manager Phil Ingram and a Designer/Programmer Chris Andrew This expansion is accompanied by a move to bigger premises at 2 Minerva House Calleva Park Aldermaston Berks RG7 4QW

More joy

Konix makers of the smooth flash and fill now very exclusive Speed King joystick have announced that production has finally caught up with demand by upping their capacity from 3 500 a week last January to 50 000 a week right now

Since the Speed King was launched many prospective customers have either had a long wait or been unable to lay hands on the device at all Now it should be freely available from computer dealers

As well as the Dragon 32 the Speed King is compatible with most other micros including many of the Amstrad models It costs £12 95 For more information (and mail order) contact Konix at Unit 12 14 Sirhowy Hill Industrial Estate Tredegar Gwent NP2 4QZ

Harris update

Harris Micro Software s BASIC42 (reviewed in this issue) has now been updated to work correctly with patched versions of Dragon DOS as well as Eurohard s versions 4 0 and 4 1 The Eurohard compatible version is designated at BASIC42 1 0(E) to cope with different locations in the Eurohard DOS

VDU OPERATORS DO IT WITH A

Patent Pending

THiNGi

computer copy holder

OUTRIGHT WINNERS
WIRRAL BUSINESS IDEA of the YEAR AWARD



PROMOTE YOUR BUSINESS HERE

Keep your name in front!

Makes an Ideal Gift - Everybody needs a Thingi!

- **Unique Velcro™ Fastening**





The Thingi creates working space out of "thin air"

- **Left hand or right hand versions.**
- **The compatible low cost solution to the problem that plagues all computer users!**

Don't struggle any longer -
GRAB YOUR THINGI NOW ! ! !

SPECIFICATION

- Scientifically designed, holds single/multiple sheets or magazines hundreds of applications not just computers.
- Completely adjustable, holds copy in optimum position to reduce neck and eyestrain.
- Will increase productivity dramatically by improving accuracy and input speeds.
- Virtually indestructible in normal use.

DIRECT ORDER HOTLINE

Your nearest Stockist is
OVERBASE LTD.
1st Floor Trace Building,
176 Conway Street
Birkenhead, Wirral L41 3JB
England
Tel: (051) 647 8981 (6 lines)
Telex 265871 MONREF G Ref 73 Mag 20290

RRP
£6.99
inc VAT

ANOTHER GREAT BRITISH PRODUCT EXPORTED WORLDWIDE • DEALER ENQUIRIES WELCOME

News desk

If you have any new products for the Dragon — software or hardware — ring the News Desk on 01-437 4343

Packet radio

Grosvenor Software have launched a major new product for radio amateurs with Dragon 32/64s or Tandy Color Computers. Known as the AX25 system. The makers say that this is the first software solution to AX25 packet radio developed in the UK for any computer.

Packet radio uses a radio transceiver and a computer to utilise other AX25 radio stations as digipeaters (digital repeaters) to send signals far greater distances than could otherwise be achieved. With satellites such as the Japanese JAS-1 (already in orbit) and PACSAT (to be launched soon) reliable world wide contact at 1200 Baud using amatuer power VHF transceivers is already a reality. The AX25 package contains complete error checking with auto retransmission where needed and can also be used on HF where the standard is 300 Baud.

A packet radio Terminal Network Controller costs around £200 — the AX25 system written by Mike Kerry G4BMK halves this by allowing a Dragon to be used alongside a conventional modem which as it is not hooked into the telephone system does not have to be BT approved.

The software comes on ROM cartridge or disc and supports 300 and 1200 Baud operation. Six contacts can take place at once with text for contact selectable on the display with full scolling even in conversation. The transparent option allows the transfer of text files and programs. Up to eight repeater stations can be specified.

A complete package with ROM software and a 1200 Baud VHF modem is available for £99. The software alone costs £49 and an HF modem adaptor will be available shortly.

Tandy computers need extended Basic and 32k minimum RAM to operate.

Grosvenor who specialise in amateur radio software also have packages available for RTTY ASCII Morse and AMTOR receive and transmit and SSTV receiving. Up to three programs can be supplied on one cartridge.

Customers should state their computer model and (if they have one) callsign when ordering. Orders to Grosvenor Software 2 Beacon Close Seaford East Sussex BN25 2JZ. Please send an SAE for further information about any of their programs or phone (0323) 893378.

Your own THiNGi

HOW many THiNGis to a NiNGi? Who cares — the British creators of the THiNGi are richer by £5000 and a slap on the back after winning the Business Idea of the Year award for their brainchild. Overbase Ltd the happy company call the THiNGi. The greatest contribution to information handling since the paperclip.

The THiNGi is actually a tiles simple little device based on Velcro and a bulldog clip for holding type copy exactly on a level with a VDU. The attraction is that the copy is upright next to the screen and won't blow away when the door opens. It reduces claim the makers neck back and eye strain and improves accuracy and typing speed. And people won't put their coffee mugs down on your copy ever again.

Quick to attach and fully adjustable the THiNGi looks like a cheap solution to copy holding as well as a convenient and versatile one. It's available in left and right hand versions and can also be customised with the name of a club or company for promotion and fund raising.

THiNGi costs £6.99 plus VAT and p&p — for further information contact Overbase Ltd on 051 647 8981.

Business books

A new guide for small business managewrs who buying their first computer systems has been published by the author Enid Mumford Professor of Organisational Behaviour at Manchester Business School.

The 78 page book Using Computers for Business Success explains in straightforward step by step terms how to anaylse business needs before choosing hardware and software how to reorganise the business environment and job specifications to make the best use of new technology.

The book is available from Manchester Business School Booth St West Manchester M15 6PB and costs £8. Professor Mumford is the deviser of the ETHICS method (Effective Technical and Human Implementation of Computer based Systems) and has written this and three other titles on setting up systems for working environments based on this method. In 1983 she was awarded a gold medal for her contribution to information science.

SEASONS GREETINGS

The staff publishers and contributors of Dragon User wish all our loyal readers and our commercial supporters a happy Christmas and a prosperous Dragon year in 1987.

The sceptics said that the Dragon couldn't survive but they reckoned without the machines own sterling qualities which has kept an enthusiastic bunch of users active. Long may it continue.

Disaster

Dragon User was intending to run several games reviews in this issue including Microdeal's Tanglewood and Quickbeam's 63098 Express and People's Chart regular Shaolin Master. Unfortunately our reviewer's disc drive went down at the wrong moment leaving him to rewrite approximately 20 pages of typed copy. The missing reviews should be back in place next month.

NDUG

The National Dragon Users Group is still going strong. Their newsletter Dragon Update appears monthly with articles reviews and technical tips. For more information contact the Chairman Paul Grade 6 Navarino Road Worthing Sussex.

Communication

Send in your questions, requests, and pleas to Communication, Dragon User, 12-13 Little Newport Street, London WC2.

Problem 1) Can you tell me if there is a way to read and load a disk in DragonDOS format with the Premier DeltaDOS because I want to make a backup of such a disk 2) Is there a way to use the Dragon in 64k mode with the Premier DeltaDOS?
Enquirer Eric de Pessemier 33 Rue Klakkedelle 1200 Brussel Belgium

Problem I want to use my Dragon 32 to communicate via a MIDI link with a Roland TR 707 drum machine I intend to use a 6850 ACIA but I need to know what function each of the pins in the cartridge port do Also I am writing a machine code program to play Othello and I would be grateful for the address of routines which perform arithmetic (including EXP(X)) and where to put the operands
Enquirer Paul Etchells 28 Pinderfields Road Wakefield WF1 3NO

Problem Does anyone know how to connect the speech chip SP0256AL 2 to the Dragon's printer port? I can't get it working
Enquirer Henk Bender Beatrixstraat 1 3286AA Klaas waal The Netherlands

Problem I require a text editor for the OS9 operating system to use with the Pascal compiler or can anyone tell me how to prepare or edit pascal files and programs?
Enquirer Mr A Durant 11 Heaton Park Road West Yorkshire BD9 5QA

Problem I can't get in touch with Steve Gathercole — has anyone got a copy or whole listing of SS RAM by Darren Eteo from *Personal Computer News* 1983?
Enquirer Philip Callaghan 54 Penkvale Road Moss Pit Stafford ST17 9EY

Problem Help and advice wanted on hacking programs etc how to discover pokes for changing program details
Enquirer A M Burton 9A Riverview Road South Benfleet Essex SS7 1JT

Problem I am in desperate need of an instruction booklet for the TEHTSTAR Do you know where I can purchase one or any of the readers of your magazine? I would willingly pay for it if necessary
Enquirer Mr R A Hall 66 Sterry Road Heathway Dagenham Essex RM10 8NX

Problem Wanted Stylograph word processor Also does anyone have a screen dump for the EPSON P40 printer?
Enquirer J Boyle 9 Inchmurrin Crescent Balloch Alexandria G83 8JJ Scotland

Enquirer Mrs L Fitzgerald 62 Langdon St Sharrow Sheffield S11 8BJ

Communication

Stuck for a routine? Need some obscure equipment? Feeling cut off? Fear not — someone somewhere can help you! Write down your problem on the coupon below (make it as brief and legible as possible) together with your name and address and send it to Communication Dragon User 12/13 Little Newport Street London WC2H 7PP We'll publish it as soon as we can — meanwhile maybe there's someone you can help this month!

Problem

Name
Address

Take command

The last part — for now — of ***Orbaum*** *and* ***Campbell's*** *machine code tutor*

ACTUALLY although we've called this the final part of the machine code epic what it actually represents is the terminal on of the first part of the series. If you hold on for a bit you may get another part.

This month we give you a list of every command you will need to program simple machine code complete with an explanation in fairly complex terms of what each command does. The explanations should be no problem if you have taken in all the other articles in this series.

Firstly though note that any assembler file must begin with an ORG command. This tells the assembler at which place in memory the assembled code is to be put. This area of memory must be cleared before use. Therefore if your program begins with the command ORG 20000 (which is where we place most of our code) then before assembling one should type CLEAR 200 19999 to clear the memory.

To assign labels storage areas the commands FCB FCC and FDB are used. For example if one wishes to use a locat on to store cursor position then the command CURSOR FDB 0 will set up a double (hence the D) precision locat on at the address assigned to the line on assembly. FCC allows entry of text to be converted for say a data table for an adventure. More details on assembler directives can be found in the manuals of most good assemblers.

Now the table (please note that this does not contain the branch instructions as they have already been covered in some detail).

ADD adds into register specified after command memory location specified after register ie ADDA $400 adds the contents of memory location $400 into A. ADDD £$400 adds $400 into D. Works with A B and D. Affects H N Z V & C flags in CC.

AND Logically ANDs 8 bit register specified with memory location storing result in 8 bit register ie ANDA $400 logically ANDs A with the contents of location $400 while ANDB £127 logically ANDs B with the number 127 thus clearing the top bit of B. Affects N & Z clearing V in CC flag.

ASL Arithmetic shift right shifts all bits in specified register one bit to the right thus multiplying register by two. A zero goes into bit zero while bit seven goes into C in CC.

ASR Arithmetic shift left shifts all bits in specified register one bit to the left thus dividing by two. Bit zero goes into C of CC while bit 7 remains the same.

CLR Sets an 8 bit register or memory location to zero. Clears N V & C and sets Z in CC.

CMP Compares two values a register and a memory address does not affect either value simply affects CC bits N Z V and C.

DEC Subtracts one from specified 8 bit register or memory address.

EOR Logically exclusive ORs a register with a memory location storing the result in the register.

EXG Exchanges the values in any two registers of like size.

INC Adds one to the content of any eight bit register or memory address.

JMP Jumps to a given address.

JSR Jumps to subroutine.

LD Loads a register from a memory address with a value through the user of £).

LEA Used for addition and subtraction within X & Y for simple programming ie LEAX 3 X will add three to X. LEAY -14 Y will subract 14 from Y and LEAX D X will take the value of D as a twos compliment number and add or subtract from X accordingly.

NEG Negates an eight bit register or a memory address.

NOG No operation. Does absolutely nothing.

OR Logically ORs register with memory location storing the result in register.

PSH Pushes registers onto stack (named as S or U).

ROL Rotate a specified register left. All bits in named register go one bit left bit zero takes carry and bit seven refills it. Therefore to shift all or register D left one must clear the carry then ROLB ROLA.

ROR As ROL only rotates right.

RTS Return from subroutine.

ST Store specified register at specified memory location.

SUB Subract contents of memory location from register.

TFR Copy the contents of specified register into second specified register. Registers must be of like size.

TST Tests a specified register or memory location to see if it is zero. Sets N & Z flags in CC.

And there you have it. The end of Part One. Hopefully if you start playing around with the commands you now know them by the time Part Two gets here you should find it really easy! Happy coding.

CRAZY SALE

OF

INCENTIVE BLOCKBUSTERS

ARCADE

BACKTRACK

DRAGON USER STAR GAME

—— 5 DRAGON RATING ——

Normal RRP £6 50

CRAZY SALE

PRICE

£2.95

STAR GAME

ADVENTURE

THE KETTRILOGY

3 ADVENTURE FOR THE

PRICE OF ONE!

Normal RRP £9.95

CRAZY SALE PRICE

£3.95

EDDIE

STEADY GO

DRAGON USER

5 DRAGON RATING

ARCADE 66 LEVELS

Normal RRP £6.95

CRAZY PRICE SALE

£3.95

ARCADE

MOON

CRESTA

5 DRAGON RATING AGAIN!

THE OFFICIALLY LICENCED

SHOOT EM UP CLASSIC

Normal RRP £7.95

CRAZY SALE PRICE

£3.95

ARCADE

CRAZY SALE ORDER FORM

Please rush me (1st Class Post)

Backtrack £2.95 ☐ **Kettrilogy £3.95** ☐ **Moon Cresta £3.95** ☐

Eddie 5teady Go £3.95 ☐

I enclose my cheque _____ please debit card no _____

Name / Address _____

_____

Incentive Software, 2 Minerva House, Calleva Park, Aldermaston, Berkshire RG7 4QW.

Orders only accepted with this form or photocopy received by 31st January 1987.

DR10

New software for review should be sent to *Dragon User*, 12-13 Little Newport Street, London WC2H 7PP.

Postman in cross-channel cheek shock!!

Program *Disk Support Tool 15 16*
Supplier Bernd Knechtel Software Arnold Wilhelm Str.9 5630 Remscheid 11 West Germany
Price £7 + £2 p&p

ANOTHER disc doctor/utility type program. This time from West German Bernd Knechtel Software for the Dragon with DragonDOS. Two versions of the program are available: version 15 is for DragonDOS 1.0 to 1.2 and version 16 is for DragonDOS 4.0 (Eurohard's ROM) in terms of options both programs are identical.

I first saw a pre-production version of this program some months ago (it was called Disk Doctor then). Since then Knechtel has added a few new options and removed a couple of completely useless ones. So for software which has been so long in development which do you get?

A completely menu driven very user friendly (almost to excess) suite of utilities called by BOOTing the disc. The first options allows a disc to be formatted - nothing very special in that except that it will also put a loading utility on the disc which allows a program to be loaded and the DOS then shut down useful for programs like Telewriter.

The second option is a 64k backup program which can also be used on Dragon 32s if you are lucky enough to have working 64k RAM chips fitted (these were on the later Dragon models). Single drive users can use this option to backup a disc with only eight swaps.

Similar to Backup is the next option Filecopy. Rather than copy the disc sector by sector it copies a file by file. This allows you to append files to a disc from another or backup a disc with some bad sectors.

A printer directory can be output using the next option including information on start length and entry addresses for machine code programs. Of course from Basic a normal directory listing can be output by typing POKE 111,254:DIR.

Option 5 is called Re-write and reads in each sector before writing it back out to the disc. The manual says it is used to refresh the contents of the disc and if you believe that...

The Rename option allows files to be renamed as in Basic but also allows the infamous null named file to be renamed.

More useful for single drive owners is option 7 Single Drive Copy. This works the same as the DragonDOS COPY command but with a single disc system copying in dividual files between discs.

The backup directory option simply copies track 20 (the directory) to track 16 (the backup directory). This is very simple to do from Basic using SREAD/SWRITE.

The majority of directory errors are caused by CC (cyclic redundancy) errors on the directory track so an option to copy the backup directory to track 20 would have been useful. Unfortunately the nearest you get is exchange directories which does the job but fails if either track cannot be read!

Finally option 10 allows you to access Basic and Dragon DOS commands (or some of them) such as CREATE, KILL, PRINT etc.

Overall there are a few useful options available in this software such as the FORMAT/LOAD utility and the single drive file copy. There are also a lot of utilities which can easily be done in one line of Basic such as the directory backup copy and the directory print.

I mentioned earlier that the program is very user friendly which is useful to begin with but tedious when you have to confirm that you want to execute a particular option several times over.

Originally this software was priced at £15 which it seems even Knechtel has now realised is too high. At half the price it is worth considering but there are a lot of other disc utilities around which offer comperable or better features. Knechtel states in the manual that if you get a faulty disc then return it with a postal order for £3 to get a replacement. What a cheek!

(A supplier who supplies faulty goods should replace them free of any charge including post and packing. Editor.)

Brian Cadge

Full support and no bugs, either

Program SuperDOS disc controller ROM
Supplier Grosvenor Software 2 Beacon Close Seaford E. Sussex BN25 2JZ
Price From £10 plus p&p (see advertisements)

GROSVENOR Software come up with epic names for their software and their new SuperDOS disc cartridge ROM chip again lives up to its name. Apart from the eradication of all bugs known to Grosvenor through their intimate knowledge of Dragon DOS and errors reported in the pages of Dragon User. This DragonDOS compatible chip is FULLY SUPPORTED — that alone makes it worth its weight in gold, so it is superb value at £10. The removal of the FE error made it a particularly worthwhile investment for me (I know that DragonDOS 4.0 removed this bug but I couldn't stand its DIR operation and couldn't boot up OS9 either.). Being fully supported I threw in a few faults that had come across that had not been corrected in early SuperDOS issues and I now have for the first time what I consider to be a totally error free DOS — and many of you must know what a bashing I give my system.

Why should use SuperDOS? Everyone with a Dragon Data or Cumana disc controller Cumana DOS users will lost the SCOPY facility but that is a minor loss compared with what will be gained. Dragon DOS 4.0 users will still be taking a giant step forward as 4.0 is still littered with bugs. Grosvenor offer a cheap fitting service for those not wishing to dabble inside their controllers themselves.

I now have for the first time what I consider to be a totally error free DOS...

Is it really DragonDOS compatible? If you have enhanced from DragonDOS 1.0 to 4.0 you will know that the end address parameter of the machine code SAVE statement has been corrected to match the originally intended cassette CSAVEM so that programs containing such a SAVE command will need to have a byte lopped off that parameter (only actually necessary if the additional byte save affects operation when the file is reloaded). Otherwise all software that references the DOS using Basic commands or the jump table will run without modification. Early versions of Disc Telewriter will need an upgrade (free) from Microdeal to the version that uses only standard DOS calls and Smithson Computing's Electronic Author (version 2.0) needs a 2 byte patch for its DIR facility to work with SuperDOS. Any other compatibility problems will be investigated as advised to Grosvenor Software.

Should you be considering investing in a disc system include the cost of SuperDOS in the evaluation — PNP Controllers come fitted with SuperDOS — as what is the point of having a faulty engine in a Rolls Royce of a disc system? That unfortunately unlike some other home micros is what we have got with the Dragon. Give your disc system a treat — give it a super duper SuperDOS.

Pam D'Arcy

Dragonsoft

New software for review should be sent to *Dragon User*, 12-13 Little Newport Street, London WC2H 7PP.

Reviewer in four letter word horror!!

Program Gordon Bennell
Supplier Smithson Computing
Price £4.99

BLAH blah blah Manic Miner clone blah blah blah Even I m getting fed up with them blah blah nicely done blah blah but who s interested in these days anyway? blah blah good sound it a bit irritating blah very good graphics blah blah clever title page blah blah but why does it have noth ng to do with the game? blah blah blah same old concept blah collect objects avoid cowpats toilets etc etc etc blah blah walk ways that fall away blah con veyor belts blah ma n problem s that it s too damn difficult blah one variation on original theme four interlinked screens must be completed as opposed to one small one to have completed a sheet blah blah doesn t add much to the program blah blah great game blah blah well designed well executed blah blah great presentat on blah who needs another Manic Miner clone though? blah give it a good rat ng cause its faultless blah blah but be warned! It s nothing new!

Jason Orbaum

(Four little dragons)

Still getting a kick out of this one

Program *Ninja Warrior*
Supplier Compulape
Price £2.95

OKAY OKAY you asked him you begged him you pleaded with him some of you sent him money the more sensible of you sent him thanks so at last Orbaum of the Warped Mind presents the re rev ew of Ninja Warrior

Firstly let me say re-reviewing is a pain in the der riere However with a good game the retread is not such a task and this s a good game The graph cs are simple in mo tion but well designed and the game is simple in concept but I have yet to see anyone com plete the fifth belt You are the N nja Warrior and as the game progresses you jump pits smash boulders with your bare feet and generally do lots of ninja type things to gain belts The game can be played by many people at the same time and I find it very good fun

I invited a group of idiots who presume that they re my friends but won t be paid for helping me with this review and we played it solidly for a couple of hours The verdict? I was the only one who liked t I believe their words were Dash this t s rather blooming bor ing but I may have m squoted them slightly

Still I like it and Compulape are plugg ng it like crazy and selling it rather cheap so I d say it s well worth while getting you hands on one

Jason Orbaum

Take note

Program *Dragon Music*
Supplier Mandian Software Birchmore Cottage Naird wood Lane Prestwood Great M ssenden Bucks HP16 0QQ
Price £3.95 each £8.95 for three

Why? asked our intrep d reviewer Dragon User don t pay up just for asking difficult questions Why is not the point These are three entirely separate performances of Scott Joplin music (1) and Bach music (2) in four part har mony played entirely on the Dragon You cannot play games with them write spead sheets with them assemble with them or indeed do anyth ng except listen to them but at £3.95 each them are cheaper than buying a whole new stereo player and quicker than waiting for the respective p eces to come up on the rad o is the point so cut the philosophy pal The public wants Scott Joplin played on a Dragon the public gets Scott Joplin played on a Dragon Don t blame us

A team of Gnomes



And now over to you, Brian

Program Decathlon
Supplier Mandian Birch more Cottage Naird wood Lane Great Missenden Bucks HP16 0QQ
Price £3.95

YOU JOIN us here at this splendid stadium for Daley Or baum s first year in this Com puter Decathlon contest And he s at the keyboard AND they re off And what a splen did event this really is Ten sim ple games but so excellently programmed Yes every one of these games is what Cascade s disappointing try four years ago should have been

And my word Orbaum s on good form today he takes the first event without a hint of trou ble getting all the purple blobs with his big white blob and sel ling I think yes-yes YES it s a new Dragonwealth record for this event now then the Anagram and oh my word what a difficult one this really is it s got eight letters and oh! won t it be disappointing to see Orbaum go down in this event on which he performed so marvellously in his trials re arranging anti disestablish mentarianism in only six seconds and OH MY WORD the timer has run out on him and he s failed on computer Still he s got the copta-landing event to go and yes I can see him pon the launch pad all ready to go and he eases I gently up but he s drifting too far and yes I m sure that he s failed on this too so three events in his competitors have a frightening lead on him but there s still the other seven to go tomorrow when hopefully we won6t have so much rain for the hangman game and the spider evas on not to men tion the other five now back to the studio

Thank you David So to sum up a good program for groups of friends playing together who aren t out for anything too complex and it s quite reasonably priced which s a relief in these days And now over the the main event of the day The Naked Editors Wrestling in Mud live from Little Newport Street out on the spot commentator is Helen Armstrong over to you Helen

The Mad Commentator

((That isn t mud Brian That is overspill from the coffee machine))

LHEX

***Malcolm Cowan** bows to OS-9 and provides a dump command for Flex*

USERS of OS9 will know the DUMP command which prints out a file in ASCII and as printable characters. The listing printed here gives a Flex version of DUMP which was originally developed for Martin Vernon of the OS9 User Group.

I called the program LHEX partly because it stands for List Hex which makes more sense than DUMP! and partly because I just liked the sound of it. You can pronounce it any way you like. I say it as if it were the LL sound in Llandudno (I assume Martin can pronounce Llandudno, seeing as he lives there.)

The program takes one parameter such as a filename. For example

LHEX 1 FRED CAL

will list the file 1 FRED CAL

P LHEX 1 FRED CAL

which will list out to the printer is as usual for the P command.

As it stands the program assumes an 80 character output as on most printers and on the Compusense Plus video board. If you want a different size of output line that can be arranged quite easily by altering the two lines

LLEN FCB 16

LINE RMB 16

These define the number of bytes to be output per line. Since each byte takes up four characters on the print line, plus the two spaces between the hex part of the line and the ASCII part, you will see that changing the two values of 16 to read 12 would make the output fit quite well on a 51 character screen.

To compile the program copy the source given into a file called LHEX TXT then enter the command

ASMB LHEX

which will create a file called LHEX BIN. This will need to be copied to your system drive and renamed LHEX CMD so that FLEX will recognise it as a new command.

The listing is annotated. Should anyone be confused by the word JIF let me explain that this is an abbreviation for JUMP IF. I picked it up from writing bits of operating system for ICL some years ago and found it a useful bit of shorthand.

```
File 1 ASMBDEFS TXT*
* Standard system definitions
* Malcolm Cowan 09/08/86
*
*  DOS Equates
WARMS  EQU  $CD03        Flex reentry point
INCH   EQU  $CD09        Low level input a char
OUTCH  EQU  $CD0F        Low level output a char
GETCHR EQU  $CD15        Input a char
PUTCHR EQU  $CD18        Output a char
PCRLF  EQU  $CD24        Print cr and lf
GETFIL EQU  $CD2D        Get file description
SETEXT EQU  $CD33        Set default name ext
OUTHEX EQU  $CD3C        Output a char in hex
RPTERR EQU  $CD3F        Report disc error
OUTADR EQU  $CD45        Output a hex address

*   FMS Equates
FMS    EQU  $D40a
FMSCLS EQU  $D403

*   System Equates
FCB    EQU  $CB40


File 2 LHEX TXT
*
* LHEX - Program to output a file in hex and literals
* Malcolm Cowan 09/08/86
* Copyright Cowan Software Ltd 1986
* This program may be used free of charge by private
* individuals for domestic purposes, and may be included
* in libraries of Public Domain Software for that purpose
* Cowan Software Ltd 10 8 1986
*
        LIB  ASMBDEFS
        ORG  $1000
        BRA  START
VN      FCB  1
LLEN    FCB  16
LINE    RMB  16          Output line for screen/printer
LTNEY   EQU  *
LINEX   FDB  LINEY       Points to 1end of input buffer
CLEN    FCB  0           No of chars actually read
CEND    FDB  0           Points to 1last char read
CLINE   RMB  2
IADDR   FDB  0           Byte count of input
END1T   FCB  1           Set nonzero when eof read

START   LDX  #FCB
        JSR  GETFIL      Get file spec
        LBCS ZA          Jif error
        LDA  #1
        STA  0,X         Open for reading
        JSR  SETEXT      Set ext of TXT
        JSR  FMS         Open file
        LBNE ZA          Jif error
AA      JSR  PCRLF       First do a n/l and
        CLR  CLEN
        LDX  CLINE       Prespaclate the char buffer
        STX  CLIME
        LDA  #
AB      STA  ,X+
        CMPX LINEX
        BNE  AB
AC      LDX  #FCB
        JSR  FMS         Read a char in
        BNE  AN          Jif exception

        LDX  CLINE
        STA  ,X+
        INC  CLEN
        STX  CLINE
        CMPX LTNEX
        BLO  AC
        BRA  BA
AN      LDA  1,X         Get error status
        SUBA #E
        LBNE ZA          Error if not eof
        STA  END1T       Else mark last pass
BA      LDA  #$
        JSR  OUTCH       Output $ and hex byte count
        LDX  #IADDR
        JSR  OUTADR      Output old value
        LDX  IADDR
        LDA  LLEN
        LEAX A,X
        STX  IADDR       Update byte count
        BSR  BA          Prepare for first pass

        LDA  CLEN        Set the end of valid input buffer
        LDX  CLINE
        LEAU A,X
        STU  CEND
BD      CMPX #LTNEX
        BHS  CA          Go to do literal output if end

        CMPX CEND
        BHS  BF          Jif past end of valid data

        JSR  OUTHEX      Output the hex nos
        BRA  BH
BF      BSR  TA          O/p 2 spaces if past valid data
        BSR  TA
```

```
8H      BSR  TA          Output a space
        LEAX 1,X
        BRA  BD

CA      BSR  SA
CC      LDX  CLINE
        CMPX LINEX
        BHS  DA          Go to end
        LDB  ,X+
        STX  CLINE
        LDA  £
        CMPB £32
        BLO  CD          Jif a control ch

        CMPB £128
        BHS  CD          Jif char > 128

        TFR B,A          Print char if SIKCHAR LE 0 else
D       JSR  OUTCH
        BRA  CC

A       TST  END1T
        LBNE AA          Go for next lines worth

        JSR  PCRLF
        LDA  £4
        LDX  £FC9
        STA  0,X
        JSR  FMS
        BNE  Z4
        JMP  WARMS       [illegible] to file

        LDX  £LINE       Reset pointer, output 2 spaces
        STX  CLINE
        BSR  TA          Output 2 spaces
        BSR  TA
        RTS

TA      LDA  £$20        Output a space
        JSR  OUTCH
        RTS

A       JSR  RFTERR      Report error, close files, exit
        JSR  FMSCLS
        JMP  WARMS

        END  START
```

The Story of C

***Brian Cadge** looks at the language which came after B*

THE C language is fast growing in popularity in the commercial programming scene — slowly gaining ground against the likes of Cobol and dBase. Although a general purpose language C is most at home in the Systems Programming environment with its control flow, data structures and low level access. It is not a very high level language in fact it includes very few built in commands, most are implemented as library functions but more on this later.

The history of C starts with the now seldom used language BCPL written by Martin Richards. In 1970 Ken Thompson developed the language B from BCPL. Both BCPL and B were typeless languages — that is there were no distinctions between variable types (character, integer, pointer etc). The only data type was a machine byte or word. B has now passed on and is not used at all in the commercial programming world. From these two languages Dennis Ritchie developed the C programming language almost as we know it today.

Due to a clearly defined standard C is a very portable language. It is not tied to any particular hardware or processor. Originally it was designed for the DEC PDP 11 running the UNIX operating system. UNIX itself has since been rewritten in C and other well known operating systems are now written in C for example GEM as found on the Atari STs.

Object code

C provides basic operators and functions to handle the low level data types found on most computers — ie characters (bytes), integers (words) and pointers (addresses). In addition floating point is also part of the standard. Most processors include facilities for directly manipulating some or all of the above data types (the 6809 handles all but I p.) directly by hardware so C can produce efficient, compact object code.

There are no built in operations to handle strings, arrays or other data types and all variables must be declared at compile time — there is no heap allocation as in languages such as Pascal. There are not even any built in commands for I/O.

The advantages of this compact language are that it is easy to define, easy to learn and easy to implement on different machines. All of the missing features are provided as functions which can be called as if they were in fact built in commands.

For the purposes of this article I used the Microware OS 9 C Compiler kindly supplied by John Penn Software. As an example of a complete (if very simple) C program take a look at figure one. This shows a program called FIND which will search an ASCII file and display any line which contains a specified string.

The program starts with some comment lines which are always enclosed in /* and */ in C. Next come the compiler directives which always begin with the £ symbol. The £include directive tells the compiler to include the ascii file (in this case stdio.h) at that point in the compilation. There can be any number of £includes in a program. stdio.h is always included as it defines certain standard I/O characteristics of the system. If you write a useful function which is often used it is worth putting in a .h file to be included in other programs.

No constants

C does not support constants as found in languages such as Pascal. The nearest you get is compile time substitution using the £define command. This tells the compiler to replace the first string with the second throughout the program text. So any occurances of TRUE will be replaced with 1 and FALSE with 0. You may have guessed that C does not support boolean variables either — any non zero value is deemed TRUE.

Variable scopes, as discussed in some detail in the Pascal article, are supported at two levels: the global and local variable. Any global variables would be defined before the definition of the first function. There must always be a function called main in any program as it is this function that is first called when the program is run. It does not, however, have to be the first function defined in the program. Any parameters are given in the brackets after the function name, these brackets are always present so if a function is parameterless one would type main() Functions may return values using the return(value) command, many functions do not however return values and therefore act simply as procedures.

The parameter types are defined immediately before the body of the function. The basic types are int, char, float, double etc. Pointers to (addresses of) types are defined by including a * before the variable name. For example to define a variable letter as a character you would use the form char letter and to define a variable string as a pointer to a character you would use char *string. This is how strings are defined in C — as pointers to the first on an array of characters.

Arrays are defined using square brackets. So char string[80] defines a string array of 80 characters (numbered 0-79). In implementation terms string is defined as a pointer so the form X=string[52] would take the address of string and added 52 to it and return to value found at that address — it is therefore identical to typing X=*(string+52) which is indeed quite legal.

Types such as FILE in the program are composite types made up of a number of elements and are defined in the file stdio.h — these will vary with different implementations of the language and so are given the name FILE in all implementations to maintain portability.

The variables argc and argv are special and contain the number of arguments passed and a list of pointers to those arguments when the command is executed. So typing the command FIND fred b ll would cause argc to have a value of 3 and argv[0] to point to FIND, argv[1] to point to fred and argv[2] to point to bill.

The commands such as printf, gets and strlen are not built into C they are implemented as functions and are to be found on all standard implementations.

All parameters are passed to functions by value not by address so it is not possible to permanently change the value of a parameter within a function (unless you pass a pointer to the value as the argument). Functions can be called recursively with a new set of local variables being generated each time.

Most variables are static variables — that is they are stored in normal memory known to the compiler. There are also variables called automatic variables which are stored (if possible) in a hardware register for increased speed.

The C structure is the main building block for data structures and may be compared to the Pascal Record. A structure is defined in C as follows:

```
struct birthday

  char name[40];
  char date[7];
  int age;
  char list[50];
```

This defines a structure type birthday consisting of the named elements and defines list as an array of 50 of these structures. A particular element is accessed in a similar way to Pascal using list[i].date etc.

The OS 9 C Compiler used for this article is worth looking at in more detail here. To use it you will need a 64K Dragon OS-9 Operating System and at least two disk drives. In addition you will need some sort of text editor to prepare the ASCII source code files — Stylograph is ideal for this purpose.

The compiler is supplied on two disks both of which must be present in the drives

GROSVENOR SOFTWARE

2 Beacon Close Seaford East Sussex BN25 2JJ Tel(0323) 893378

ALLDREAM - DSKDREAM

ALLDREAM: the most highly acclaimed Dragon machine code development system, containing:-
A powerful full-screen text editor, a comprehensive multi-pass assembler - a disassembler - and a complete machine code debugging and learning aid featuring memory and register examine and change, testing with breakpoints (up to 10 concurrent) and extensive trace facilities through RAM or ROM.
ALLDREAM tape £12.95 Cartridge £24.95 DSKDREAM - Dragon/SuperDDS version with disk I/O £19.95
DREAMPRT An adaptor giving 64 character print lines for letter/report writing £3.50
DREAMREF Prints a sorted list of all labels/addresses used in a DREAM assembly. £3

NEW - DSKDREAM in ROM!

Imagine the advantages in having the facilities of DSKDREAM always available in ROM, freeing 8K RAM space. Now it can be fitted inside all DDS controllers except Delta DDS (sorry!).
Due to space restrictions, the breakpoint and trace facilities are omitted from the ROM.
For £5 extra will will supply in addition a full DSKDREAM on disk.

CumanaDDS 1.2 onwards: A 16k ROM for you to fit yourself, with SUPERDDS & DSKDREAM	£19
Or send your controller to us (well wrapped) for a re-fit	£20
DragonDDS. Send your controller to us for an 8K to 16K ROM conversion adding DSKDREAM	£14
OR we can fit SUPERDDS plus DSKDREAM for	£20

SUPERDDS: A totally DragonDDS compatible disk operating system - but without the bugs!
Strongly recommended as a replacement for DragonDDS or CumanaDDS 1.2 onwards.
Recommended by Pam D'Arcy! Compatible with telewriter, Basic42 etc etc.

Supplied as a ROM to fit yourself, with full fitting instructions	£10
Or send your controller to us for a same-day return service	£12

A Programmer's Guide to DragonDDS. The only source of detailed information on the workings of Dragon/SuperDDS. A full DDS memory map, details of the directory tracks, details of all routines in the DDS that can be called from machine code, with programmed examples. £2.50

D.R.S. DATA RETRIEVAL SYSTEM

A full-featured database program suitable for all sorts of filing and record keeping purposes. Data files may be kept on tape or disk (Dragon/SuperDDS). DRS features a full screen editor, user definesable screen layouts, and powerful search, add, ammend, delete, sort and printer report facilities. DRS is written wholly in machine code making it the fastest and most professional database program available for Dragon computers. Tape (transferable to disk) £9.95

AMATEUR RADIO SOFTWARE

RTTY: feed audio from a short-wave receiver directly into the cassette port, and see international news agencies, weather reports, shipping information decoded by our software appearing on your TV. Add a tone-demodulator to receive radio amateurs also. Program on tape £12
CW: Receive and send Morse code. Program features automatic speed tracking with lock facility. Sending speeds up to 200 wpm. Needs a demodulator (see below). Program on tape £10.75
AMTOR: Full FEC and ARQ transceive software only needing an RTTY terminal unit and clock/PTT unit. Tape £29 Cartridge £39. Receive only tape £19. Cartridge with AMTOR RTTY and CW £59
TONE DEMODULATOR for RTTY CW and AMTOR £22 complete with lead / Dragon connector.
TONE GENERATOR for RTTY/AMTOR transmission £15 AMTOR clock/PTT unit £17.25

AX25 PACKET RADIO. The UK's first software solution to this exciting mode. Only the 3rd such system in the world. Halves the cost of a plug-in-and-go AX25 system. Fully scrollable screen display with each QSO individually selectable makes multiple connections easy.
Software only (cartridge/disk) £49. Packaged with 1200 Baud VHF modem £99
Software supports 1200 and 300 Baud. HF modem adaptor available soon.

State callsign (if any). Send SAE for further details. Add 40p P&P. (£1 Europe, £3 elsewhere)

FIGURE 1 - A Simple C program

```
 *      FIND.C - This program lists the lines of a file
                 which contain the string prompted for.
*/

#include <stdio.h>
#define TRUE  1
#define FALSE 0

main(argc,argv)
int argc;
char *argv[];

{
FILE *fp;
int line;
char search[80],string[256];

if (argc != 2)
  {
  fprintf(stderr,"Usage: FIND pathname\n");
  exit(1);
  }
fp=fopen(argv[1],"r");
if (fp==NULL)
  {
  fprintf(stderr,"Cannot open file %s \n",argv[1]);
  exit(1);
  }
printf("FIND 1.0\nEnter Search String: ");
gets(search);
if (strlen(search)==0) exit(1);

line=0;
while (fgets(string,255,fp))
  {
  line++;
  if (findstr(1,string,search))
    {
    printf("%5d %s \n",line,string);
    }
  } /* end while loop */
fclose(fp);
} /* end main */
```

for a program to be compiled. Executable OS 9 commands are the output from the compiler. Efficient code is produced — only routines used within the program are actually included in the runtime code produced.

Split compiler

Due to memory limitations the compiler has been split into two passes for OS 9 level one and so can take quite a long time to compile even a simple program. Even with the two pass version of the compiler there is not enough RAM left to run the 51 column screen whilst using the compiler, although compiled programs can of course use this screen.

The compiler supports almost all of the standard UNIX system calls including os9fork for parallel process running. All of the features of OS 9 are available through the system calls which make this compiler a very powerful systems language for any serious OS 9 programmer.

The error reporting and recovery seem quite powerful and all error messages are usually self explanatory.

A potentially very useful section of the manual deals with the linking of program modules written in other languages, particularly BASIC 09 to C code. Therefore it will not be necessary to scrap all of your favourite routines written in BASIC 09 in order to move up to C.

Once again it has only been possible to give a very brief overview of the C language but enough I hope to encourage you to look further at this programmers language.

System Used: Microware OS 9 C Compiler

Requires: 64K Dragon, Dual Drives, OS-9 Operating System and Text Editor

Supplier: John Penn Software, Dean Farm Cottage, Kingsley, Borden, Hants GU35 9NG (Tel: 04203 5970)

Price £27

NEW — PI-6809



Could this be the answer to a prayer? PI-6809 is a **PC compatible 6809 co-processor** It features ONE MEGABYTE of RAM 128K Eprom space RS232 port and has a full FLEX system on board (OS9 support soon!) PI-6809 allo9ws you to use DRAGON FLEX disks on a PC Compatible and to create and store files on the PC It allows full access to PC floppy disk hard disk networks printer and uses the PC display and keyboard Can you afford to ignore the keen pricing and vast resources of the PC market? **NOW YOU CAN USE THE MOST POPULAR MICROCOMPUTER IN THE WORLD** while retaining the software benefits of your DRAGON system If you want to know more then CALL OR WRITE FOR MORE DETAILS

DRAGONPLUS

Update YOUR Dragon to 128K memory with an 80 column display Hundreds of satisfied customers Installation service available Requires DRAGON64 (CALL US for details of 32K upgrades) Software to drive DRAGONPLUS is available in cartridge DRAGONDOS FLEX and OS9 formats

DRAGONPLUS	— 103.50
FLEX or OS9 drivers	— 5.75 each
EDIT + 80 col BASIC	14.95 (cartridge or disk)

FLEX SOFTWARE

Get the most out of your DRAGON with FLEX is in our opinion the BEST way to use a DRAGON computer for serious applications

FLEX Editor/Assembler/DBASIC		— 99.99
DYNACALC spreadsheet		— 49.50
RMS Database		—49.50
SPE word processory editor		— 65.00
*** COMPLETE PACKAGE	***	— 199.00
LUCIDATA PASCAL		— 75.00
CHATPLUS 2 modem software		—24.95

HARDWARE

CALL US for best prices on disk drives We give you 10 free diskettes and a VERY FAST SERVICE

CUMANADOS disk controller cartridge	— 75.50
RACE EPROM PROGRAMMER	— 78.00
BLANK cartridge — 16K capacity	— 5.00

BARGAINS

EDIT + CARTRIDGE or DISK for DRAGON32/64	— 8.95
DASM/DEMON CARTRIDGE or DISK for DRAGON32/64	— 8.95
** 10 FLOPPY DISKS — certified double density	— only 9.95 **

**** ALL LISTED PRICES INCLUDE VAT ****
***** POST AND PACKING 2.00 per order. *****

VISA

FAST MAIL ORDER

Telephone
01-882 0681 (24 HR)
01-886 6936

COMPUSENSE

PO. BOX 169
286C GREEN LANES
PALMERS GREEN
LONDON N13 5XA

DR16

Basic 42

Harris Micro Software's new package reviewed by **Ron Coates**

THE Dragon's normal text display of only 32 x 16 upper case characters is undeniably very poor and outdated by just about any other home micro on the market today making the machine unsuitable for displaying more than the most basic information. Even the simplest word processor requires a display beyond the capabilities of the Dragon as we know it. The answer has always been to use the hi-res graphics screen and draw each character as required. This is a reasonable solution until you try to scroll the screen for listings or use standard Dragon facilities such as PRINT@ etc.

A basic rule of thumb says that the home micro of tomorrow is the business micro of today. A look at today's business machines will reveal windows, pull down menus and lots of other clever goodies, all normally beyond the Dragon.

Good news

Well, having depressed every Dragon owner south of the North pole the good news has come from Harris Micros in the form of a package for 64 owners running DragonDOS called BASIC42.

The BASIC42 package is probably the best step so far towards alleviating these problems without loss of compatibility with existing software. BASIC42 is not simply another hi-res text utility but as described in the accompanying manual is the central core of an operation system which will help bring the Dragon up to date. The package comes on disc and simply requires the BOOT command to bring it to life with a hi-res screen displaying the usual copyright emessage and an OK prompt.

BASIC42 copies both the BASIC operating system AND the DOS software into RAM where it can easily be hacked, sorry, altered to suit the user's requirements. This is achieved by using the Dragon's memory map type 1 which configures the Dragon to be 64 glorious K of wonderful RAM, not a byte of ROM in sight! Because the entire system is now in RAM, the BASIC42 software is loaded into memory above the DragonDOS software and so does not deprive BASIC of a single precious byte.

Having booted the BASIC42 system and looked at the usual 42 column hi-res display, it looks like many other hi-res utilities, but a few minutes experimenting reveals that this is probably the fastest hi-res screen driver written for the Dragon, and turning the pages in the manual reveals all sorts of well thought out additions to the normal system. In fact there are so many features of the BASIC42 system it would have been far easier to simply reprint the manual. The character set, being in RAM, may be changed to one of several supplied on the system disc by simply issuing the command USE FRENCH SET or alternatively an entire character set may be created or edited using the supplied program DRAWCHRS.

No more fiddling

A major improvement in the use of this system is the ability to enter commands in either upper or lower case characters, which means no more fiddling about with that horrible SHIFT/0 combination which I am sure has beaten all of us at some time or another. All keys now have an auto repeat feature which may be disabled or altered by simply poking a few memory locations specified in the manual. Unlike many other hi-res drivers, it is very easy to revert back to the normal display by using the command TEXT and back again to the hi-res display using the command hi-res. Simple, eh?

It is nice to see that this driver has been very neatly interfaced with the rest of the Dragon's operating system and pressing the RESET button shows this as the display remains quite happily in the hi-res mode with the cursor patiantly flashing away.

Possibly one of the most important features of BASIC42 is its support of the now highly fashionable windows. There are a total of ten separate windows available to the user, eight of which may be easily redefined by the user through the FRAME command to suit any particular application. For the uninitiated a window is a section of the screen which may be used as a completely separate screen in its own right and which may be cleared and scrolled without affecting the rest of the screen. This feature is perfect for the programming of pull down menus etc. Windows 0 and 9 are not redefinable by the user since window 0 is the whole screen and window 9 is a special screen that has its own memory in order that it will not destroy what was on the screen in that area before the window was called.

Cursor positioning and character highlighting have been included in this package in the form of simply commands such as ROW, COLUMN and UNDERLINE with cursor position reporting being available through commands such as REPOS and COLPOS which return the current row and column of the cursor. The state of the current window may also be interrogated with the HEIGHT and WIDTH commands. A rather clever command CATCH allows you to access one window while actually being in another, a useful example of this being given in the manual. This shows how a Basic program may be run in one window with any error messages appearing in the other, very useful when debugging a program.

The operating system itself is only very small in terms of memory usage, and so there is an area of some 3.5k available in which to load utility programs. No doubt more of these utilities will become available from Harris Micros as time goes by, but there are two immediately available, HELP and SPOOL.

The HELP utility allows the user to change easily features of the BASIC42 system such as the auto repeat speeds, setting of control keys and the screen scroll mechanism. The enabling or disabling of the BREAK key is also achieved through the HELP utility. HELP also provides a much improved TRON utility which redirects the line number printed by the TRON routine to the top right hand corner of the current window so that normal output from a program is not corrupted and the PAUSE command enables a program or listing to be used in single step mode so that the effect of each line can be decided before continuing. HELP also provides expanded error messages so no more funny error messages like ?SC error in line 100 to add to the confusion! While installed in memory, the HELP utility will also give details of the commands and functions of BASIC42.

The other utility, SPOOL. The other utility, SPOOL. I had to say it twice *(I hope that caught you lot out as well — Ed.)* cos I didn't believe it at first! At long last someone has sat down and written a printer spooler for the dear old Dragon. Although a decent commercial printer spooler buffer will have between 64k and 128k of buffer memory, the 3.5k used by SPOOL is 110% better than the standard system. As soon as there is less than 3.5k of data to be printed, the Dragon is once again available for use while the SPOOL utility looks after the printer. Any print job may be aborted by simply typing SPOOL OFF (now there's a new result for you).

Software range

For the Dragon owning business user the extra good news is that the Harris range of business software (MONEYBOX, CASHBOX etc.) will all work with BASIC42 providing that a patch program BOXPATCH is used, giving far better screen displays. Unfortunately I have not seen these programs running and so cannot say just how improved they are.

In conclusion, BASIC42 transforms the Dragon into a decent system for use by small businesses or Basic users.

For the effect this package has on the Dragon it is well worth the asking price and the utilities are remarkable, well priced at £5.00 when you consider that on average a blank disc costs between £1 and £2. I sincerely hope that this system will get the recognition it deserves.

Program BASIC42
Supplier Harris Micro Software
Price £14.95. Utilities £5 each

Shuffleword

Anagrams galore for you to solve in this game by ***P Marlow***

SHUFFLEWORD is an anagram game that gives the player anagrams to solve. The player chooses the length of each anagram (there are two four six eight and ten letter words). Then a choice is given whether music plays or not. Then a word is chosing at random from a list held in the DATA statements and an anagram is made of the letters.

The player is given ten guesses at the original word. If the word is guessed correctly the first time then bonus points are awarded. If the word is not guessed after ten times the correct word appears on screen. A count is kept of how many times the player presses ENTER for each word. If the count goes up to ten for a word penalty points are deducted from the player's score — a random number of points between one and ten. So you cannot calculate how many points you can afford to lose!

The title screen uses the anagram routine to draw anagrams of the title SHUFFLEWORD onto the hires screen.

The DATA statements each contain twenty words but this can be altered by changing dimensions FOUR$ SIX$ EIGHT$ and TEN$ if line one twenty and altering the FOR next loops in lines one forty one seventy two hundred and two thirty.

If there are any problems I can supply a copy of SHUFFLEWORD on cassette for £3.00. As I have only a Tandy CoCo Dragon owners will have to use the Dragon/Tandy conversion program listed in the December 1984 issue of Dragon User.

(Photocopies of the December 1984 article are available from Dragon User as usual price £1.)

```
10 '*****************************
20  ******* SHUFFLEWORD ********
30 '****** BY P  MARLOW ********
40  ******** 01 6 86 ***********
50  ***** 30  IME  CENCE ********
60  ******** BENTLEY ***********
70  ******** WALSALL ***********
80 '****** WE I MIGHTS *******
90 '******** W 2 OUI ***********
100  *****************************
1 0  CLEAR 1000
20 D M FOUR$ 20),SIX$(20),EIGHT$(20),TE
N$(20) Z$(84) I$(83)
130 P L  PC 32 GOSUB 1000 GOSUB 1200
140 FOR  1 TO 20
150 READ FOUR$(F)
160 NEXT F
170 FOR S 1 TO 20
180 READ SIX$  S
190 NEXT S
200 FOR E 1 TO 20
210 READ EIGHT$ E
220 NEXT F
230 FOR T 1 TO 20
240 READ TEN$
250 NEXT  T
260  L
270 PRINT TAB(10)  SHUFFLEWORD
280 PRINT TAB(10)
290 PRINT PRINT THE COMPUTER WILL CHOOSE
 A WORD AT RANDOM,  ,
300 PRINT  YOU  AN CHOOSE THE
310 PRIN  NUMBER OF LETTERS IN THE WORD

320 PRINT  (EITHER 4,6,8 OR 10 LETTERS)

330 PRINT  THE  OMPUTER WILL  SHUFFLE IT'
S  WORD
340 PRINT  AND YOU MUST GUESS  THE
350 PRINT  ORIGINAL  WORD YOU HAVE TEN
   GUESSES-
360 PRINT@448  HOW MANY LETTERS
370 N$ INKEY$  N$     THEN 370
380 SOUND 100,1
390 N VALUE$ IF N=1 THEN N=10
400 IF N 4 OR N 6 OR N 8 OR N 10 THEN 44
0
410 PRINT@448     NVALID CHOICE  TRY AGAI
N ,
420 FOR X 1 TO 1000:NEXT X
430 GOTO 360
440 PRINT@448, MUSIC ON (Y/N) ?  ,
450 O$ INKEY$ IF O$=   THEN 450
460 SOUND 100,1
470 IF O$  Y  OR O$  N  THEN 490 ELSE 48
0
480 PRINT@448, INVALID SELECTION  TRY AG
AIN  FOR X 1 TO 1000 NEXT X:GOTO 440
490 IF O$  Y  THEN J 1 ELSE O 0
500  IF GOSUB 900
510 PRINT TAB 10),  SHUFFLEWORD
520 PRINT  AB 10)
530 QU 0
540 PRINT  JUMBLED WORD IS  ,A$
550 FOR X 1 TO 10
560 PRINT  GUESS NO  ,X,  NPUT G$:IF G$
   THEN UL  UL+1
570 GOSUB 8 0
580 NEXT X
590 IF R 1 AND O 1 THEN PRINT  WELL DONE
 YOUR SCORE IS ,SC PLAY  T8B04C03B04L03
ABGAE#T4G8T UP T8O4C DELD03B04 D3ABGT4F#A
T/DI6T3EF#6DE #6EH#GHAEF#GHAGMABO4L03B04
LLELO3H#6UGBT4 GOTO 640
600 IF R 1 AND O 0 THEN PRINT  WELL DONE
 YOUR SCORE IS SC
610 IF QU  0 THEN PRINT  YOU CHEATED , C
HEAT RND SC PRINT USING  ### ## ,CHEAT,
 PRINT POINTS DEDUCTED  R 1=QU 0-SC SC (
CHEAT CHEAT 0
620 IF R 0 AND O-1 THEN PRINT  SORRY THE
 ANSWER WAS  ,C$ SC SC N PLAY  ET4P60EP6
0M#ET 160E T4GH#F#EEDMT2E  PRINT  YOUR SC
ORE IS  SC ELSE IF R=0 AND O 0 THEN PRI
NT  SORRY THE ANSWER WAS  C$ SC SC N PR
INT YOUR SCORE IS ,SC
```

```
630 FOR X=1 TO 1000 NEXT X
640 PRINT@448,"ANOTHER GAME (Y/N) ?"
650 F$ INKEY$ IF F$-   THEN 650
660 IF F$- Y  THEN PRINT STRING$(13 [illegible]
 SOUND 100,1 GOTO 690
670 IF F$  N  THEN 680 ELSE 650
680 SOUND 100,1 CLS4:PRINT@26[illegible], 'THANK-Y
OU FOR PLAYING',:FOR T T TO 15 SCREEN 0,
1:FOR Y 1 TO 300 NEXT SCREEN 0,0 FOR Y=1
 TO 300 NEXT Y,T CLSRND(8) END
690 GOTO 360
 0 REM SHUFFLE
 10 ( RND(20) A$  " C$-" .R-0
720 IF N 4 THEN A$-FOUR$(C) Q=4
730 IF N-6 THEN A$-SIX$(C) Q-6
 0 IF N 8 THEN A$ EIGHT$(C) Q-8
 0 IF N 10 THEN A$=TEN$(C) Q=10
760 M Q*100
770 C$ A$ J$  "
780 FOR K 1 TO LEN(C$)
790 L LEN(A$)
800 P RND(L)
810 J$ J$+MID$(A$,P,1)
820 A$ LEFT$(A$,P-1)+RIGHT$(A$,L-P)
830 NEXT K
840 IF J$=C$ THEN 710
850 A$ J$
860 RETURN
870 REM CHECK
880 FOR H=1 TO 10
890 IF G$ C$ AND X-H THEN GOSUB 920
900 NEXT H
910 RETURN
920 IF X-1 THEN SC=SC+10+RND(M) X 10 R 1
-RETURN
930 SC SC+INT(10/X)
940 X-10.R-1 RETURN
950 REM WORDS
960 DATA BAST,CHAR,CRAG,EVER,EXIT,FOIL,F
ORD,FORE,LEGO,MASK,MAUL,MULE,MUSK,PERT,S
OFK,SHAG,TEAK,TILT,TOBY,ZULU
970 DATA ADDICT,APACHE,AZALEA,BLOUSE,CDR
OM,CORYZA,COURSE,IAMBUS,INTONE,MINUTE,P
ERIOD,PILFER,REVERE,SHABBY,SIGNET,TANNER
,TRIBLE,VACATE,YORKER,ZYGOTE
980 DATA ANALECTS,ASTONISH,CASSETTE,COMP
UTER,CONDENSE,CONTRAST,DULCIMER,HARMONIC
,KILOGRAM,MARZIPAN MELINITE,PRIMEVAL,REC
ORDER,SEMESTER,SNAMBLES,TRAINING,WARRIGA
L,WEDGEWOOD,XENOGAMY,ZOOPHYTE
990 DATA ,ANTITOXINS,BELLADONNA,BRIGNINE
SS,COMMODORES,DICTIONARY,EXPERIMENT,INIT
IALISE,LANUGINOUS,MANCHESTER,MATHEMATIC,
MICROPHONE,MONAMMEDAN,PRIMORDIAL,REFEREN
CES,SHENANIGAN,TELEPHONES,TELEVISION,TRA
NSISTOR,WELLINGTON,XENOPHOBIA
1000 Z$(65)  BR16R8F16D40L8U24L24D24L8U4
0E16RD8BR4F12D4L24U4E12"
1010 Z$(67)  BR8R24F8D8L8U4H4L16G4D32F4R
16E4U4R8D8G8L24N8U40E8
1020 Z$(68) "R32F8D40G8L32U56BF8R20F4D32
G4L20U40
1030 Z$(69)- R4D8L32D16R24D8L24D16R32D8
L40U56"
1040 Z$(70)='R4D8L32D16R24D8L24D24L8U56
1050 Z$(72) "R8D24R24U24R8D56L8U24L24D24
L8U56
1060 Z$(73)='8R8R24D8L8D40R8D9L24U8R8U40
L8U8'
1070 Z$(75)- R8D24E24R8G2BF28L8N24D24L8U
56
1080 Z$(76) 'R8D48R32D8L40U56
1090 Z$(77) 'R8D12F12E12U12R8D56L8U36G12
H12D36L8U56
1100 Z$(78)-'R8D12F24U36R8D56L8U12N24D36
L8U56
1110 Z$(79)- BR8R24F8D40G8L24H8U40E88D8B
R4R16F4D32G4L16H4U32E4"
1120 Z$(80) "R32F8D16G8L24D24L8U56BF8R20
F4D8G4L20U16"
1130 Z$(82)  R32F8D16G8L16F24L8H24D24L8U
56BF8R20F4D8G4L20U16
1140 Z$(83)  8R8R24F8D8L8U4N4L16G4D8F4R2
0F8D16G8L24N8U8R8D4F4R16E4U8N4L20H8U16E8

1150 Z$(84)  R40D8L16D48L8U48L16U8
1160 Z$(85)= R8D44F4R16E4U44R8D48G8L24H8
U48
1170 Z$(87)- R8;D36;E12;F12;U36;R8;D56;L
8;U12,H12,G12,D12,L8;U56'
1180 Z$(89)- R8D12F12E12U12R8D16G16D24L8
U24H16U16"
1190 RETURN
1200 X 3 Y 0 AA$  WELCOME TO
1210 GOSUB 1270:GOSUB1400
1220 AA$- SHUFFLEWORD  FOR Q 1 TO 2 GOSU
B 1310 GOSUB 1400 NEXT Q AA$ "SHUFFLEWOR
D  GOSUB 1270:GOSUB 1400
1230 AA$=    GOSUB 1270 GOSUB 1400:AA$-
HIT ANY KEY  GOSUB 1270.GOSUB 1400
1240 S$ INKEY$.IF S$    THEN 1240
1250 SOUND 100,1
1260 RETURN
1270 FOR I-1 TO LEN(AA$)
1280 I$(I)=MID$(AA$,I,1)
1290 NEXT I
1300 RETURN
1310 K$ AA$ M$- '
1320 FOR K-1 TO LEN(K$)
1330 L LEN(AA$)
1340 N-RND(L)
1350 M$ M$+MID$(AA$,N 1)
1360 AA$=LEFT$(AA$,N 1)+RIGHT$(AA$,L-N)
1370 NEXT K
1380 AA$-M$
1390 GOSUB 1270.RETURN
1400 PMODE 3,1 SCREEN 1,0
1410 DRAW  S2
1420 FOR Z-1 TO LEN(AA$)
1430 COLOUR RND(4)
1440 IF COLOUR 2 THEN 1430
1450 DRAW  C +STR$(COLOUR)
1460 DRAW  BM +STR$(X)+ , +STR$(Y)+Z$(AS
C(I$(Z)))
1470 X X+23
1480 NEXT Z
1490 Y Y+32 X 3
1500 RETURN
```

DRAGON & TANDY COLOUR OWNERS . . . 3 NEW RELEASES

CUTHBERT & THE GOLDEN CHALICE

Legend tells of a fabled GOLDEN CHALICE that can bring wealth and long life to whoever it belongs being placed at the end of a deep cave. Having heard these tales Cuthbert sets off to try and collect the chalice but will he succeed where many others have failed. The cave is filled with deep pits that will mean instant death should he fall in. Other hazards include poisonous snakes, swarms of fast moving bees and giant deadly spiders. Will you be able to take on the challenge and guide Cuthbert to the GOLDEN CHALICE.

DRAGON 32/64 TANDY COLOUR 32K CASSETTE £5.95

TANGLEWOOD

If you go down in the woods today
You've never played an adventure like TANGLEWOOD! There are five characters for you to control, each one of which behaves differently and has different problems for you to solve. At the same time you must avoid contact with the evil Schark who will continually try to thwart your plans. There are over 700 accessible locations in nine sections all in colour graphics: the woods, Dwarf Dive (platforms, lifts and ladders), Schark castle (a 3-D maze on five floors) and six smaller text only sections. The entire game loads at once. TANGLEWOOD provides many helpful features including the ability to return to a previous position without having saved it to tape. There is no sudden death and although it is possible to get yourself completely stuck you have to be very careless to do so. TANGLEWOOD is also a real-time game and some things are possible at night which are not during the day.

TANGLEWOOD ON CASSETTE FOR DRAGON 32/64 & TANDY COLOUR 32K £5.95

WIZARDS QUEST

If you've played Atic Atac on the Spectrum then you'll love WIZARDS QUEST! As Arcade Games go this must be one of the all time greats.

WIZARDS QUEST ON CASSETTE DRAGON 32/64 TANDY COLOUR 32K £5.95

Name Address

Post to

Please send me
- ☐ Tanglewood
- ☐ Cuthbert & the Golden Chance
- ☐ Wizards Quest
- ☐ Post & packing 75p

microdeal
ELECTRONIC PUBLISHING

Box 68
St Austell
PL25 4YB

Credit Card Orders
by phone 0726 68020

NEW RELEASES
HALF PRICE!

YES NOW YOU CAN PURCHASE ALL OUR NEW RELEASES AT LESS THAN HALF THEIR REGULAR PRICE BY SIMPLY JOINING OUR *DAY 1* CLUB

IF YOU HOLD A MAJOR CREDIT CARD THEN YOU SIMPLY FILL IN THE ORDER FORM BELOW AND WHENEVER WE RELEASE A NEW LINE FOR THE DRAGON/TANDY COLOUR WE WILL SEND YOU A COPY AT HALF PRICE ON DAY 1 AND CHARGE IT TO YOUR CREDIT CARD! YOU MUST UNDERTAKE TO TAKE AT LEAST 6 NEW RELEASES BUT AFTER THAT YOU CAN CANCEL AT ANY TIME.

YOU KNOW AS A PREVIOUS CUSTOMER OF MICRODEALS THAT ALL OUR PRODUCTS ARE OF HIGH QUALITY AND WORTH PURCHASING. ALL OUR FUTURE RELEASES WILL COST £5.95 AND YOU PAY ONLY £2.95 PLUS OUR REGULAR 75p POST & PACKING, SO SIGN UP NOW!

I would like to become a member of the ***DAY 1*** Club and agree to allow Microdeal to charge £2 95 at regular intervals against my credit card

Credit Card Type *Access/Barclaycard/American Express/Diners

Credit Card Number _____ Expiry Date _____

Tick here if you want the latest releases sent straight away ☐

Signed _____

Delete

Post to

Box 68, St Austell PL25 4YB

Name _____

Address _____

_____

_____

Post Code _____

Expert's Arcade Arena

Write to The Expert' of Dragon User 12-13 Little Newport St, London WC2H 7PP with all your arcade tips and hints

YES it's that time of year again when treetops glisten and children listen to hear the sleighbells in the snow Yes it's novelty song time it's ceaseless adverts for Transformers (robots in disguise) time it's compilations and Bond films time it's getting far too drunk and pigging out on far too many birds (*he means turkeys — Ed*) it's old people freezing to death in their unheated council houses while you buy Auntie Henrietta a bottle of perfume the size of a pea for fifty quid it's a time of trying to work out just how much money you're going to get so you can make a profit by spending less than that amount on everybody else Yes It's Capitalist Christmas time! (Actually you'll probably be reading this in November when you won't even have started to worry about the number of 'shopping days left!!)

And so in the true Christmas spirit (that of the pleasure of receiving) before I give you all my present here's a list of gifts I'd like to receive from various people out there Some of them are rather silly but you'll notice that there's a list of Games at the beginning These are games that I don't possess a copy of and so cannot really write much about so if anyone has one they really can't stand any longer (or just want to suck up to me) I suggest they donate it to your truly

THE EXPERT'S CHRISTMAS LIST

A car sticker with I don't even want a Porche written on it

A vast sum of money (bigger that any of you possess so don't bother with this one)

A time share flat in Nicaragua

No more letters in stupid luminous pen (especially you Andrew Ridgely)

Copies of *Astro Blast Cosmic Cruiser Cave Fighter Dunkey Monkey Death Mines of Sirus Galactic Raiders Horace Goes Skiing Invaders Revenge Moonhopper Morrison Chess, Quazimodo Sea Dragon* and *Space Raiders*

More maps (when em I going to get one of *Brock's Kingdom?*)

More of those sort of letters that say I wish your column was 20 pages long

More of those letters that come with a big bottle of gin with them

More of those letters that come with millions of cigerettes

In fact send anything you can lay hands on!

A "PRIZE" (of the usual Arcade Arena standard) will be sent to the person who sends the most stupid present to the above address! (Oh darn And I was going to demand a percentage Ed)

Now here's my presents for you Firstly this rather splendid *Fantasy Fight* map drawn by M Borthwick (who suggests that I em in fact 'The great blue writer Ardvark of Arbu — Completely wrong so no prizes there)

Secondly the great POKE LIST

ASTRO BLAST Colour 21067

BEANSTALKER Access code is REGISTER answer NO to tape go back to main screen hold down X/ENTER/6 to go to editor Clear/N to go to next screen Clear/X to increase lives Colour 27780 Reset 27801

BUBBLE BUSTERS Once running a game press reset then play again and bubbles fall in order

BUZZARD BAIT Poke 21093 &HE0 to get PMODE3 SCREEN 1 0 CSAVEM BUZZARD 7168 32755, 7168 *** No dongle required on re-load *** Reset 20360

BEAM RIDER Crash with RESET POKE 7783, LIVES or POKE 11840 13 for infinite lives EXEC 7683.

CAVERNS OF CHAOS PIGLET when playing E for next screen Colour 26660 Lives 26665 (Zero for infinite)

Colour Poke this location to 224/232/240/248 to give Green 4 colour/buff 4 colour /Green & Black/White & Black

COSMIC CRUISER Lives 9398 Zero is infinite

CU*BER Lives 10454 Reset 20481

CUTHBERT IN THE COOLER Lives 8925 (up to 14)

CHAMBERS Lives 133339

CAVE FIGHTER Lives 27078 (zero equals infinite)

CRAZY PAINTER Let space invader reach the bottom when paint reaches zero leave it and you have an infinite supply

DUNKEY MUNKEY Lives 15120 Colour 19862

DARK PIT Pause game press 8/L/M/C Use cursors and Enter to select a screen position man same way and restart Lives 11255

DUNGEON RAID Press C to continue on screen you just finished on

DANGER RANGER Lives 10510

DEATH MINES OF SIRUS Codes are CBLW & TLL

ESCAPE Code is 79245

EDDIE STEADY GO Lives 27152

FEARLESS FREDDIE Lives 28052 Reset 20363

GALACTIC RAIDERS Lives 19664

HUNGRY HORACE Stay on park bell lives and score soon mount up Guard can't get you when you're both in the tunnel

HORACE GOES SKIING Colour 28356

ICE CASTLES Go into tunnel on screen one on first go jump thus giving yourself 140000 points and getting onto a level somewhere between 20 and 30 Lives 19160 Colour 13071 Reset 12290

INVADERS REVENGE Lives 14719 Reset 11571

JET SET WILLY While game is in progress press keys M/A/X together flick through screens with cursors press space position Willy (sorry Ed!) press space to continue

JET BOOT COLIN Colour 7329 Reset 12336 Infinite lives POKE 6759 77 POKE 9099 77

THE KING SKIPF CLOADM FOR X=12850 to 12894 PRINT X POKE X 255 NEXT X EXEC This gives hundreds of lives!

LUNAR ROVER PATROL Lives &H5728.

MUDPIES Colour 22902

MANIC MINER PENGUIN to get boot Colour 13825 Lives 13146 (up to 25)

MOON HOPPER Colour 12827

MORRISON CHESS Crash with reset then POKE 8401 224 EXEC 7700. Im proves colour drastically

NINJA WARRIOR Lives 9489

PLANET INVASION Lives 7438.

PEDRO Use SKIPF SKIPF CLOADM to load then any of Seeds — 23603. Bricks — 23620 Stop tramp — POKE 16047 125 Run with EXEC

PENGON Infinite lives — POKE 11633 125.

QUAZIMODO Lives 15644

ROBIN HOOD Lives 15712 Colour 19884

ROMMEL'S REVENGE Lives 16516 Reset 23724

Reset This location should be poked to zero for warm start

RUBY ROBBA POKE 21117 125 (infinite time) Lives 22014

SEA DRAGON Colour 20599

SHOCKTROOPER Poke 17075 125 (infinite lives)

Pause game Press SHIFT/0 then R then SHIFT/S to make yourself invulnerable to bullets

SPACE RAIDERS CLOADM 32000 POKE 32184 57 EXEC 32159 POKE 2304 lives (up to 45) EXEC 16384

SCREAMING ABDABS Colour 10999 (232 only)

TEA TIME On the sugar cane screens you can't be hit in the top left corner Infinite lives — POKE 19996 109

TIM LOVE'S CRICKET Use a Quickshot 11 play computer bowler as far down as possible arm top left bowl gives a full toss at top of off stump

TUBEWAY ARMY Lives 12367 Stage 12388 (1-6) Reset 12301

ZAK'S SUN Lives 16670

That's all folks Merry November

Fantasy Flight
The Map



Switching joysticks

A simple hardware modification by **Stephen Denning**

READERS with switching joysticks may be interested in the following simple circuit to enable them to use them with their Dragons. I was able to build it into a Quickshot 1 joystick with only minor PCB modifications for about £1.00. As readers will doubtless be aware the Dragon joystick ports are read via 6 bit A to D converters which return 64 different values for voltage levels between 0 volts and 5 volts. Dragon joysticks are normally the potentiometer type wired between 0 volts and 5 volts (figure 1) which send a voltage corresponding to the joystick position from the slider of the potentiometer to the relevent joystick input (referred to as JOYSTICK 0 to 3). Most games are programmed for three joystick positions, ie (for JOYSTK 0) left, centre and right, which reduces the need for voltage levels to 3, which are 0 volts, 2.5 volts and 5 volts. The 2.5 volts can easily be obtained with a potential divider and the 0 volts can be obtained by connecting the 2.5 volts to earth with the Left switch, but the 5 volts is marginally more technical.

In figure 3 the potential divider is formed by R1 and R2, whose junction is connected to the JOYSTK 0 input. The lower end of R2 is connected to the collector of TR2 which is normally held hard on by R3. Thus with a centred joystick TR2 collector will be as near to 0 volts as makes no difference and the JOYSTK 0 input will be at 2.5 volts as R1 and R2 are equal. If the Left switch is closed it earths the JOYSTK 0 input which then becomes 0 volts. If the Right switch is closed it earths the base of TR2 thus switching it off. The JOYSTK 0 input is then connected to the 5 volt supply via R1 and is thus effectively 5 volts. R1, R2, R4 and R5 are 5.6kohms. R3 and R6 are 4.7kohms. Any type of NPN general purpose transistor can be used for TR1 and TR2. In the case of the Quickshot 1 there is ample space on the PCB to glue the transistors and resistors on to it and hard wire them as required. This circuit can be used in any switching joystick that has all the switches switching to earth and can be adapted to work with any other type. Great care should be taken with the wiring as it is possible to short circuit the 5 volt supply in the computer with expensive consequences. Otherwise, a cheque for £6.50 made out to S. Denning and sent with the joystick to me at the above address will cover the cost of parts, return postage and covers on.

This type of joystick is not fully suitable for software that requires a proportional input, eg Flight simulators — it does work with Speedracer but makes it awkward to select circuit 3 and adds a certain brutality to the steering response.

(Editorial note: opening or altering a joystick within its warranty period will normally invalidate the warranty in case of breakdown.)



Figure 1 DIN plug seen from rear

Parts list

R1,2,4,5 5.6kohm resistor
R3,6 4.7kohm resistor
TR1,2 any general purpose NPN transistor
Epoxy adhesive
solder
fine insulated wire



Figure 2 Standard joystick



Figure 3 Final circuit of modified joystick

Disc to Tape

Save disc space by backing up your data on cassette says ***Peter Whittaker.***

ALTHOUGH I started using my Dragon with only a slow cassette recorder I eventually upgraded to a disc drive which I would now be unable to do without. Unfortunately discs are a lot more fragile than cassette tapes. Even in the most careful of hands a disc can fall victim to a cup of coffee or to someone sitting on it. While a cassette tape might survive the event a disc will be completely destroyed so disc users are advised to have backup copies of all their discs.

To backup all my discs to disc would cost quite a lot of money and would be a waste of discs I couldn't use. However the alternative of trusting to luck that they will remain undamaged for ever is also unappealing. As a solution to the problem I have written this program to transfer all the contents of a disc to a cassette tape. It uses less than twenty two minutes of tape to record a forty track disc so four discs can be saved on one C90 cassette. This enables one to have copies of all one's discs for much less than a quarter of the cost of duplicate discs.

The program works by protecting memory above 9500 and copying the contents of the disc five tracks at a time into the protected area. This is then saved to tape as a machine code file. Eight files are required to save an entire disc. Each file has the same name identifying the disc it comes from and a number telling which of the eight files it is. So a UTILITY disc would be saved as UTILITY1 UTILITY2 UTILITY3 and so on. To restore a disc the program runs in reverse. Each file is reloaded into protected memory and then copied back out to the relevant track and sector.

When RUN the program displays an option list. Press the <S> key and then place the disc to be saved in the disc drive. Place the cassette in the tape recorder and set it to record. Now type in the disc title remembering that only the first seven letters will be used. (The last space is used for the file number.) Now go and have a [illegible] while the program transfers the disc to tape. Whilst it runs the program will display the Track and Sector number it has reached at the top of the screen. When the disc has been saved the program will print a message saying so, play a tune and then return to the options list. Press the <Q> to quit.

When a disc gets damaged and you want to restore it from tape run the program and press the <L> key. Insert a disc in the drive and ready the tape recorder to load the data back in. Type in the name of the files to be loaded and then go have another cup of coffee whilst it runs. Once again the program will print the Track and Sector number it has reached at the top of the screen. When the disc has been reloaded the program will print a message saying so, play a tune, print out the DIRectory and then stop.

Program Explanation

There is little fancy prgramming in this routine. The sectors are loaded using two of the disc ROM routines. Simply POKE 236 DISC TRACK(0-39) POKE237 DISC SECTOR (1-18) POKE238/9 STARTSAVE/LOAD ADDRESS. Then EXEC40409 to copy the next 256 bytes to the selected track and sector or EXEC49412 to copy the selected sector down into memory.

```
10 CLS0 CLEAR200 9500
[illegible]
    OUT PRINT [illegible] 9500 E DISC TO
    TAPE PRINT [illegible] LOAD DISC E
    ROM TAPE PRINT [illegible]
[illegible]
[illegible] E #
[illegible] E P$=IF"THEN [illegible]
[illegible] IF P$=[illegible] THEN 80
[illegible] IF P$=[illegible] THEN 260
70 GOTO 30
80 MOTORON PRINT[illegible] DISC TO TAPE
    [illegible] PRINT PRESS [illegible] TO B
    EGIN DISC [illegible] INPUT ENTER TIT
    LE OF DISC TO SAVE [illegible]
90 MOTOROFF
100 [illegible] TO 39 STEP 5
110 FOR COUNT=0 TO 4
120 TRACK=STOCK+COUNT
130 FOR SECTOR=1 TO 18
140 POKE236 TRACK POKE237 [illegible] TRA
150 [illegible]COUNT*4608+(SECTOR-1)*3
    56
160 POKE238 INT(LD/256) POKE239 LD-
    PEEK(238)*256
170 EXEC 49412 'LOAD SECTOR FROM DI
    [illegible]
180 PRINT38 "TRACK " TRACK PRINT31
    [illegible] SECTOR [illegible] SECTOR
190 NEXT SECTOR COUNT
200 WAIT 5000
210 [illegible]SAVEM A$ 9500 [illegible] 41134
```

```
[illegible]
[illegible] DISC TO TAPE
[illegible] FOR S=1 TO 5 FOR B=100 TO 10 ST
    EP-10 SOUND B [illegible] NEXT [illegible]
[illegible] S [illegible]
[illegible] [illegible] TAPE TO [illegible] STEP
    [illegible] PRINT ENTER TIT E OF DIS
    TO [illegible]
[illegible] E P [illegible] TO [illegible]
[illegible] CLS0 [illegible]
[illegible] FOR [illegible] TO 1
[illegible] TRACK=BLOCK+COUNT
[illegible] FOR SECTOR=1 TO 18
[illegible] POKE236 TRACK [illegible] SECTOR
    [illegible]COUNT*4608+(SECTOR-1)*3
    56
[illegible] POKE238 INT(LD/256) POKE239 LD-
    PEEK(238)*256
[illegible] EXEC 49409 [illegible] SECTOR TO DISC
[illegible] PRINT31 "TRACK " TRACK PRINT31
    [illegible] SECTOR " SECTOR
[illegible] NEXT SECTOR COUNT
[illegible] WAIT 5000
[illegible] [illegible] "
[illegible] FOR S=1 TO 3 FOR B=100 TO 10 ST
    EP-10 SOUND B 1 NEXT B B
[illegible] DIR
[illegible] [illegible] 1986 [illegible] WHITTAKER
```

Text Screen Dump

***Mike Hides** gets lower case into ASCII and out onto the printer*

THE PROGRAM is to dump the contents of the text screen to a printer. The program works by examining the locations 1024 to 1535 and sending the appropriate ASCII code to the printer. The difficulty in writing this program was that the Dragon only stores the *uppercase* letters in ASCII format. The program can be located anywhere in memory and is executed by using the address of the first instruction (Listing 1).

The program looks at the locations 1024 to 1535 in turn and puts the contents in the A register. If the contents are between 64 and 95 they are sent to the printer unchanged. This is because they are the correct ASCII codes. The JSR $800F is a ROM routine for sending the contents of the A register to the printer. If the value in A is below 63 the TOLOW loop adds 96 to its value which produces the correct ASCII code. The TOHI loop works in a similar way but subtracts 64 to obtain the correct ASCII code. The GRAPH loop is a trap for codes which the Dragon uses for block graphic characters which cannot be correctly interpreted by printers. They are converted to ASCII code 32 which produces a SPACE on a printer. The B register is used to check when a line has been completed and sends code 13 to produce a carriage return every 32 characters. The loop BACK decreases the contents of the B register every time a character is sent to the printer.

Listing 1

```
        ORCC    #$50
        LDX     #1024
LINE    LDB     #32
LOOP    LDA     ,X+
        CMPA    #63
        BLS     TOLOW
        CMPA    #96
        BHS     TOHI
        JSR     $800F
BACK    DECB
        CMPB    #0
        BNE     LOOP
        LDA     #13
        JSR     $800F
        CMPX    #1535
        BLE     LINE
        ANDCC   #$AF
        RTS
TOLOW   CMPA    #27
        BHS     GRAPH
        ADDA    #96
        JSR     $800F
        BRA     BACK
TOHI    CMPA    #128
        BHS     GRAPH
        SUBA    #64
        JSR     $800F
        BRA     BACK
GRAPH   LDA     #32
        JSR     $800F
        BRA     BACK
```

Listing 2 — Basic Loader

```
10 CLEAR 200,31999
20 FOR N = 32000 TO 32066
30 READ A$
40 POKE N,VAL("&H"+A$)
50 NEXT N
60 DATA 1A,50,8E,04,00,C6,20,A6
70 DATA 80,81,3F,23,19,81,60,24
80 DATA 20,BD,80,0F,5A,C1,00,26
90 DATA EE,86,0D,BD,80,0F,8C,05
100 DATA FF,2F,E2,1C,AF,39,81,1B
110 DATA 24,12,8B,60,BD,80,0F,20
120 DATA E3,81,80,24,07,80,40,BD
130 DATA 80,0F,20,D8,86,20,BD,80
140 DATA 0F,20,D1
```

To save CSAVEM"DUMP",32000,32066,32000

To initiate the progam use EXEC32000.

LAST MONTH I promised you I d get back to dealing with letters but here I am beginning by breaking my promise Can you trust no one these days? Well it s not my fault there have been two interesting and cheap adventures released this month and I will have space to deal with some of your letters before the end of the column Promise

First past the starting gate is The Thirteenth Task at just £3 from Arc Software 272 Mearns Road Newton Mearns Glasgow G77 5LY This is definitely one for wimps with ambitions as you get to play the part of Hercules and don t ask which part Not content with the fabled Twelve Labours of Hercules Arc Software has decided to give him a thirteenth job to do and that s killing Hades the ruler of the Underworld Could be unlucky for some

Herculean tasks

If you know about Hercules s previous problems then that ll be a help as some of them re eppear and a knowledge of Greek mythology won t come amiss either A neat 4 page inlay is provided with the tape and author Alan Cook has obviously gone to a lot of trouble to present a decent looking product so three cheers for that The inlay provides a good introduction along with some of the verbs the game understands though a full list would be better as some of the others are just a little out of the ordinary SLAUGHTER STRANGLE LEASH SLAY and THROTTLE for example and these also give you a flavour of the violent nature of the game though that s just a reflection of the violence of Greek mythology itself Rambos e seven stone weakling when compared to the ancient Greeks However e help sheet and full verb list is available from Arc Software and also from myself if you happen to be writing to me

I promise I didn t look at the sheet when playing the game though and I have to say that its main drawback is that it seems to be comparatively easy At least to begin with though the problems were getting more complex when I ran out of time and actually had to start writing about the adventure The games got 135 locations and this is made possible by a bit of repetition in the descriptions used Quite how all those Alpine paths got to ancient Greece I m not sure! After dealing with a lion in the first location you wander off and spy a hind this is what s known as hindsight I suppose a useful thing in any adventure Trouble is the hind senses you and runs away but it can be cornered somewhere and will then earn you a few points A few weapons are picked up you encounter the Graeae (three hags with one tooth between them like a geriatric Beverly Sisters) through the Minotaur s maze and out the other side to deal with old favourites like the Hydra Gorgon Muses and Cyclops

The vocabulary supports LOAD SAVE HELP SAY EXPLAIN EXAMINE and other useful commands all of which can be abbreviated to the first three letters although the character set hasn t been redefined so the screen layout is a little pedestrian But well worth investing three quid in despite my few criticisms

For £3.95 you can have a copy of Underbeings of Croth from Mardian at Birchmore Cottage Naridwood Lane Prestwood Great Missenden Bucks HP16 0QQ and this is also worth parting with your hard earned pennies for This time the character set has been redesigned and also the screen so that the text scrolls up through appropriately enough a scroll Presentation is excellent all round with dramatic music to accompany the instructions and this slowly fades when you press ENTER to start the game proper

The story? You have discovered the secret entrance to an underground village but unfortunately the village s guardians have also discovered you and you begin the game in an iron cage suspended by a chain above a dark pit from which rather violent roars emerge Get out of that as they say Then make your way to freedom The first task has that nice balance of difficulty so that it takes you a little time to accomplish it but not so hard that it puts you off Just examine everything and think whether some objects might have more than one use

If you can get out of the next few locations (don t linger down below) you ll promptly thrown into a cell and the map around here shows some nice touches of reality as you come across doors that can only be opened from one side then later on you might find yourself on the other side and able to open the door to pass through Watch out for the ape-guards although I haven t yet met the Tochtworms the cassette cover promises And I never will if I don t devise a way of getting the box out of the well without getting myself trapped at the bottom And how can I get the owl to give up the shiny object in its beak especially as I m told I can t climb trees?

The atmosphere of an underground village is well-evoked and this game too supports lots of useful commands Not just GET EXAMINE SAVE LOAD SEARCH SAY and so on but multi-inputs linked by the word AND and the program also understands the word IT to refer to the previous object e g TAKE BOX AND OPEN IT There s a FAST option if your Dragon can cope with the high-speed POKE and all in-all this is another for Dragon adventurers to add to their Christmas shopping lists

Entanglements

Some of you in fact lots of you have already been shopping for Tanglewood and I've had many letters praising that game so anyone who s not yet bought it is obviously missing out Simon The Solver Hargrave has come up with lots of clues though he hasn t yet managed to finish it completely To get Peabody home go to the north eastern garden get the spade then dig in NEDRAG NRETSEW and put what you find in ESUOH GOD EHT To get rid of the ants YSNAT WORHT To get gold coin tell GABNAEB to DNOP OTNI EVIO and search for it It is there promises Simon To make rockcakes first LLIM MORF RUOLF TEG and SEKAC KOOC in NEHCTIK EGATTOC DOOWGOD

Simon asked for help on Colossal Cave where he was unable to get his last treasure the bear s chain Just NIAHC TEG though you need SYEK EHT to do it Simon s happy to help with this list of adventures Tanglewood Wizard s Quest Vortex Factor Trekboer Juxtaposition Ring of Darkness Return of the Ring Colossal Cave Keys of the Wizard El Diablero Madness and the Minotaur Franklin s Tomb and Lost in Space Plus some others he says The man s a glutton for punishment and you can punish him by letter plus s a e to Crawley Hill Farm Uley Dursley Glos GL11 5BH by phone on 0453-860361 after 4 p m weekdays only or on Prestel mailbox 453860361 Finally he says if there are any other Dragon owners playing the multi-user game Shades then try to contact him as Cuthbert as he needs your help!

Proving that Simons are far from simple comes a letter from Simon Harrison of The Vicarage 56 Norwich Road Walton Thetford Norfolk NR25 6DB This one s just polished off Syzygy as well as Dragon

COMPUTAPE

27 COOMBE ROAD SOUTHMINSTER, ESSEX. CMO 7AH

TEL: 0621 772589

VISA

ACCESS

WOULD LIKE TO WISH ALL OUR CUSTOMERS A VERY MERRY XMAS AND NEW YEAR MANY THANKS FOR YOUR SUPPORT

SOFTWARE PROJECTS

Mario Mine
Jet Set Willy
TWIN PACK — £7.95 (OR £5.00 EACH)

DESIGN DESIGN

Dark Star
Rommels Revenge
TWIN PACK £7.95 (OR £5.00 EACH)
Tubeway Army £2.99

INCENTIVE

Back Track £5.50
Pole Position £7.95
Lady Steady Go £6.95
Laser Costa £7.50

MASTERTRONIC

Sigma Dive £1.99
Vega Jackpot £1.99

HEWSON CONSULTANTS

3D Lunattack £2.99
3D Space Wars £2.99
3D Seiddad Attack £2.99

PEAKSOFT

Tim Loves Cricket £5.00
NEW Champions £7.95
Photo Finish £3.00
Osiris £3.00

OCEAN

Hunchback ONLY 1.99

ADVENTURES

INTERNATIONAL TWIN PACKS
Stranger Oddessy
Adventure and Mission
Dick Adventure
Jack Castle
Lady Hawk House
Mandrake Doom
Jack Town
Dragon Village
Savage Island — Part 1
Savage Island — Part 2
Hulk
Sword of Clay Cattle
Machine
Escape From Pulsar 7
Death — Part 1
Death — Part 2
Legend
Legend and Andromeda
Zaccaria Alpha
CHOOSE YOUR TWIN PACK FROM THE ABOVE TITLES FOR ONLY £7.50 per Twin Pack

NEW! NEW!

NICKS SOFTWARE

Sand Adventure and 4D
BOTH FOR ONLY £3.95

COMPUTAPE

Madness & the Monotaur £2.99
Hi Speed SAE + £0.50

IMAGINE

Pedro ONLY — £1.99

MICROVISION

The Talisman £7.50
Beanstalk £7.50

BLABY GAMES

Kung Fu — The Master
Boulder Crash £5.00
Temple of Doom £5.00
Cosmic Crusader £5.00
Olympia £3.99
Gis A Jeb £3.99
Sword & the Sorcerer £3.99
Morbid Mansion £3.99
Caverns of Chaos £3.99
Fingers £3.99
Tuth (4 Games in one) £3.99
Wizards Lair £3.99
Starman Jones £3.99
Karma Crazy £3.99
Detonate/The Alien £2.99
Hubert £2.99
Bors the Bold £1.99
Ruby Robba £1.99
Star Swoop £1.99
Bombs Away Baker £1.99
MacDougals Last Stand £1.99
The Bells £1.99
Laser Run £1.99
Desperado Dan £1.99
Mutant Wars £1.99
Dalis £1.99
Star Defence £1.99
Perilous Pit £1.99
Blocks Kingdom £1.99
Dodo £1.99
Copia Snatch £1.99
Barmy Burgers £1.99

ARCADE GAMES

PROGRAM FACTORY

Ninja Warrior £2.99
Taskship £2.99
Piecdrop £2.99

B & H SOFTWARE

Pub Crawl £3.99
And All Because £3.99

A & F SOFTWARE

Chuckie Egg £2.99
Screaming Addabs £2.99

THE END OF A CLASSIC
ONLY 350 CHUCKIE EGG LEFT
AND 150 SCREAMING ABDABS!

IMPSOFT

Chicken Run £1.99
Fruity £1.99
(OR £3.50 THE PAIR)

C.R.L

Keys of Roth £1.50

CABLE SOFTWARE

Quazmodo £1.99
Zaks Son £1.99
Superbowl £1.99
Fantasy Fight £2.99

COMPUTERWARE

Lunar Lander £3.50
Snooker Jump £3.50
Book Puzzles £3.50
Blockbuster 2 £6.50
Wordsearch £4.50

COMPUTAPE

Whirlybird Run £2.99

MELBOURNE HOUSE

Horace Goes Skiing £1.99
Hungry Horace £1.99
(NO INLAY CARD)

MICRODEAL

Frogger £1.99

OASIS

Chess £2.99

SOFTEK

Ugh £2.99
Galactians £2.99
Ultrapede £2.99

ROMIK SOFTWARE

Rom Cube £1.50

RICHARD SHEPHARD

Transylvanian Tower £1.50

TUDOR WILLIAMS

Accs High
The Attack £1.50
(OR £1.00 THE PAIR)

WINTERSOFT

Rites of Darkness £5.00

MISSION ONE

Project Volcano £1.99
(Become a Spy for a day)

PERIPHALS + EDUCATIONAL

JOYSTICKS

CONSUMER
ELECTRONICS
Pal Strike Control
Joysticks £19.95
PEAKSOFT Multi Direction Joysticks — £5.50 EACH £9.95 PAIR

CABLES

Cassette Lead £2.50
Centronics Printer Cable £11.95
Aerial Lead £2.50
DUST COVERS £2.99

EDUCATIONAL

MERIDIAN SOFTWARE

Spelldox £5.95
Mazeracce £5.95
Underbridge of Cloth £5.95

SULIUS SOFTWARE

Besieged £2.99
World Power £2.99
(Two programs to aid spelling from 7 years and upwards)

CROUCHER COMPUTER SOFTWARE

CAD 3d £4.95
A computer aided design program to help you design your own screens

BOOK SALE!

THE DRAGON TRAINER £2.50
Learn basic on your Dragon with simple step by step instructions

DRAGON 32 GAMES MASTER £2.50
A great help to all those writing their own games. It covers sound, graphics, colour movement, scoring and many other items

THE WORKING DRAGON 32 £2.50
A collection of programs covering topics such as data storage, finance, household management, educational and games of skill

ADVANCED SOUND AND GRAPHICS £2.50
This book describes all the major aspects of sound and graphics on your computer from 3D projections animation, screen saving through to keyboard sound synthesis

ARTIFICIAL INTELLIGENCE ON YOUR DRAGON 32 £2.50
How to implement AI routines on your computer and turn it into an intelligent machine with which you can even hold a conversation

ORDER 2 BOOKS OR MORE FOR ONLY £2 EACH

UTILITIES

HARRIS SOFTWARE

Moneybox (Personal Accts) £14.95
Mailbox (Mailing List) £16.99
Sharebox (Stocks and Shares) £16.95
Salesbox (Sales Ledger) £19.95
Billbox (Purchase Ledger) £19.95
Cashbox (Nominal Ledger) £19.95
Stockbox (Stock Control) £19.95
Orderbox (Invoicing) £16.95

SMITHSON COMPUTING

Electronic Author Word Processor — ONLY £14.95
Discovision — £19.95
Very good value for money
Fake Bank £6.95

ASTROCALC — Astrology

Learn how to calculate a horoscope
SPECIAL PRICE — £9.95

OCCULT SOFTWARE

Numerology OUR PRICE — £6.50

PAMCOMMS

Source Make £8.00
Disckit — Diagondos £10.20

ELKAN ELECTRONICS

Dragon/Tandy Colour Counter £7.95
Convert Basic Dragon Programs to Tandy and vice versa

FOR A FAST MAIL ORDER SERVICE send your order to the above address making all cheques Postal Orders payable to COMPUTAPE
For Catalogue only please send SAE OR TELEPHONE 0621 772589
FOR 24HR CREDIT CARD SALES

Prices include FIRST CLASS POSTAGE and packing OVERSEAS ORDERS WELCOME

COMPUTAPE The only Software Company to make your Dragon Chips fry not cry!

PLEASE REMEMBER XMAS LAST POSTING DATES
UK — 19th December — ABROAD — 20th December

Mountain and Calixto Island. He'll help on those and would love to hear from anyone able to help him solve his biggest problem which is how to prise his sister away from Chuckie Egg so he can use his Dragon again!

C Vollbracht of 110 Alpine Rise, Styvechale Grange, Coventry, West Midlands CV3 6NR needs someone's help as he's having difficulty buying cop es of Fishy Business, Lostin Space, Death Mines of Sirius II, Had a Million and Miss on Moon base. Anyone willing to sell? He (or maybe she) is prepared to help for the usuals a e on Williamsburg, Mansion, Final Countdown, Eno, The Golden Baton and The Emperor Must D e.

Looking for openings

Keith Marshall is in danger of losing his sanity he says unless someone can tell him how to get a light in The Vortex Factor open the door in Pyramid of Doom and open the gate in something called 1200. In return he can assist on Danger Island, Mystery of the Java Star and Aquanaut 471.

Needing help on Syzygy is Ian Barford, 79 Hertford Road, Stevenage, SG2 8SE, and Ian also asks about the Adventurers Club Ltd which I recommended several issues ago. In fact the club seems to have gone out of business, despite g ving excellent value-for money service for over a year and although there is talk of it getting going again soon I wouldn't suggest anyone send off any money to them for the moment. If you're already a member you'll be aware of the long summer silence and promises of an autumn return.

If you want to sample the Adventure Contact club run by Pat Winstanley then you'll only need to fork out 50p for a sample issue of their monthly newsletter. The aim of this club is different. It isn't a helpline but is a more of a forum for adventure writers who want to share ideas and hints. Inevitably this means a bit of concentration on successful u tilities like The Quill and Graphics Adventure Creator, not available to Dragon users but there are also articles on marketing games, royalties, duplication, cost of cassette covers and so on. Worth it if you're seriously interested in that side of things.

Stephen Hoolon, 4 Bankcroft, Longton, Preston, Lancs PR4 5AL wants help on Tanglewood, like how to get the shrimp net and what uses the scanner and Paul Marsh asks if anyone else is playing some lesser known adventures. Horror Castle and Pirates Ahoy. If so contact Paul at 7 Earlsmead Crescent, Cliffsend, Ramsgate, Kent CT12 5LQ.

Calling Tunbridge Wells calling Tunbridge Wells. Any Dragon owners out there? If so contact Richard Tyler, 11 Madeira Park, Tunbridge Wells, Kent TN2 5SX. He needs help on Rings of Darkness, Wings of War and Juxtaposition, particularly as his SAVE/LOAD command won't work in that last one. Anyone know why he might be getting a syntax error when he tries to use it? Richard has finished Aquanaut 471 and offers help on that one.

More problems of an unadventurous nature this time on Castle Adventure for Gary Alford, 35 Victoria Road, Fair Oak, Eastleigh, Hants SO5 7FY. His version keeps crashing with an OM error despite using the POKE 25 6 and NEW commands before loading. Anyone else experienced that problem and more importantly solved it?

Neil Bowden's having trouble with The Sorceror of Claymorgue Castle and would appreciate help at 73 Erskine Hill, Polmont, Falkirk FK2 QUH, while Philip Ravenscroft wonders how he'll ever defeat Vader in Syzygy. Philip lives at 40 Cedar Road, Willenhall, West Midlands WV13 3BZ.

Finally if you've got access to Prestel then you might like to try calling up The Drag Mag run by Simon Jones and at present the only Prestel magazine devoted to the Dragon. He (yet another Simon) says that there's a large section devoted to adventuring which recently featured an interview with someone called Mike Gerrard. Now that has to be worth looking at and can be looked at on page x700110161. And if anyone has worked out why so many people called Simon are into Dragon adventuring then please let me know as I'm quite baffled.

Adventure Contact

To help puzzled adventurers further we are instituting an Adventure Helpline — simply fill in the coupon below stating the name of the adventure, your problem and your name and address and send it to Dragon User, Adventure Help line, 12/13 Little Newport Street, London WC2H 7PP. As soon as enough entries have arrived we will start printing them in the magazine.

Don't worry — you'll still have Adventure Trial to write to as well!

Adventure .....

Problem .....

.....

Name .....

Address .....

.....

Adventure contact

Adventure Calixto Island
Problem I cannot get the paddles
Name Simon Kennerley
Address Duxmore Farm, Newport, Isle of Wight, PO30 2NZ

Adventure Trekboer
Problem How do I land on the planet?
Name Laura Hodgson
Address 6 Gordon Place, Kinross, Tayside, Scotland

Adventure 1) Juxtaposition 2) Tiekboer
Problem 1) Where is the red cette ore? 2) How to stop Xendos plant from dying?
Name David Kelsall
Address Woodlop Farm, Goosnargh, Preston, Lancs PR3 2ER

Adventure The Cricklewood Incident
Problem How do I travel by bus or train?
Name Scott Taylor
Address 14 Pembroke Gardens, Wellesbourne, Warwicks CU35 9PX

Adventure 1) Juxtaposition 2) Tiekboer
Problem 1) Where is the recieve sender and deeds of the brown? 2) How do you get past the forcefield?
Name James Baker
Address 3 Haycock Road, Bangor On Dee, Wrexham, Clwyd, North Wales

Adventure Return of the Ring
Problem How do you get the key of the genie on the forest moon?
Name Wayne Holt
Address 10 Thirlemere Road, Bedworth, Nuneaton, Warwickshire CV12 8BY

BLABY COMPUTER GAMES

This may well be your last chance to buy at these silly prices as we are unfortunately discontinuing Dragon Games

✪ MORBID MANSION	£2.50
❑ COSMIC CRUISADER	£2.50
☆ RUBY ROBBER	£2.50
✪ OLYMPIA	£2.50
✪ WIZARDS LAIR	£2.50
☆ STARMAN JONES	£2.50
✪ TRUN	£2.50
☆ CAVERNS OF CHAOS	£2.50
✪ FINGERS	£2.50
✪ GIS A JOB	£2.50
✪ SWORD AND SOURCERER	£2.50
KAMA KA	£2.50
✪ KUNG FU	£3.50
☆ TEMPLE OF DOOM	£3.50
☆ BOULDER CRASH	£3.50
❑ BELLS	£1.00
❑ PERILOUS PIT	£1.00
☆ MUTANT WARS	£1.00
✪ BARMY BURGERS	£1.00
✪ BORIS THE BOLD	£1.00
✪ DARTS	£1.00
✪ BOMBS AWAY BASIL	£1.00
✪ McDOUGALS LAST STAND	£1.00
❑ MISSION ATTACK	£1.00
❑ BROCKS KINGDOM	£1.00
❑ DO · DO	£1.00
☆ COPTA SNATCH	£1.00
❑ STAR DEFENCE	£1.00
❑ DESPERADO DAN	£1.00
❑ LASER RUN	£1.00
✪ STAR SWOOP	£1.00
✪ FRUIT MACHINE	£1.00

Please Add 50p for Post and Packaging on each game up to four games

BOULDER CRASH — Boulder to the right and left nfacl every where, nows your chance to be a D amond Miner a thing you ve always nodout wanted This game was a h t on all other compulers now you have t Arcade Action **£5.00**

N E W

MISERS DREAM

From
The Author of
"EDDIE STEADY GO"
£4.00

N E W



TEMPLE OF DOOM — Jones must collect all the keys from this castle to escape four floors of wander ng thats! f you can last the test of time 3D Arcade Action **£5.00**

Blaby Computer Games
Lutterworth Road
Blaby, Leicester
Telephone: 0533 773641

✪ Denotes Five Star Review
☆ Denotes Four Star Review
❑ Denotes Three Star Review

Send S A E for Catalogue

If you've got a technical question write to Brian Cadge. Please do not send a SAE as Brian cannot guarantee to answer individual inquiries

Dragon Answers

Second language

I HAVE a Dragon 64 computer and am interested in using the second Eprom socket for an alternative language. Is this possible and could you explain how to select the second on board Eprom and say the addresses in the address space?

Russ Taylor
Chepstow
Gwent

IT WOULD be possible to replace the second Basic Eprom (used for Dragon 64 Basic) with a new language eprom which you would have to write and blow yourself. The second Eprom is selected by making bit 2 of $FF22 an output and then setting it low. The original rom can be reset by setting this line high. The new rom appears in the address space $8000 to $BFFF. The following machine code will select the second rom and enter it at address $8000 with interrupts disabled.

DRCC	#255
LDA	$FF23
ANDA	#$FB
STA	$FF23
LDB	$FF22
ORB	#4
STB	$FF22
ORA	#4
STA	$FF23
LDA	$FF22
ANDA	#$FB
STA	$FF22
JMP	$8000

How to justify

I HAVE a Dragon 32 and printer and want to try some word processing. I've thought of buying a piece of commercial software but have decided to try writing a simple WP myself. The first problem I have to come up against is how to right justify a line to 51 characters. I would imagine that I need to use a for of LEFTS and RIGHTS commands but I can't quite see how.

Would it be possible for you to write a short routine to perform right justification on a string?

Sandra Robinson
50 Kennington Way
Orpington
Kent

THE following subroutine can be used within your word processor to right justify lines. The line length is set up in the variable LN in line 500. The string to be justified should be in A$ when the routine is called. It will be returned justified in A$.

```
500 LN=51 P=51
510 DF=LN LEN(A$) IF
INSTR(A$,  )=0 THEN 570
520 IF DF=0 THEN 570
530 FOR J=P TO 1 step -1 IF
MID$(A$,J,1)=  THEN
A$=LEFT$(A$,J)+MID$(A$,J) DF
=DF-1 GOTO 550
540 NEXT J
550 P=J-1 IF p<1 THEN
P=LEN(A$)
560 GOTO 520
570 RETURN
```

Input using?

IN THE same way as Dragon Basic has a PRINT USING facility to provide formatted output I would like to know if there is such a thing as INPUT USING which would provide an input mask for text and number input?

A M Stein
8 Suffolk Road
Seven Kings
Ilford
Essex

THERE is no built-in input using command on the Dragon but it would be relatively simple to provide this in Basic. As an example look at the routine below which will take numerical input as formatted in the string FS and return the value in V. This could be expanded and improved to include error traps and all the useful format functions available with Print Using.

```
100 CT=0 M$=
110 I$=INKEY$ IF I$=  THEN 110
120 IF I$=CHR$(8) AND CT>0
THEN
CT=CT-1 M$=LEFT$(M$,CT)
?CHR$(8)  CHR$(0) GOTO 110
130 IF I$=CHR$(13) THEN 190
140 IF MID$(F$,CT+1,1)=  AND
I$<>  THEN SOUND
50,1
GOTO 110
150 IF MID$(F$,CT+1,1)= £ AND
(I$< 0 OR I$> 9) THEN SOUND
50,1 GOTO 110
160 ?I$
170 M$=M$+I$ CT=CT+1 IF
CT<LEN(F$) THEN 110
180 V=VAL(M$) RETURN
```

Double take

I RECENTLY acquired a Dragon 64 and 80 track double sided disc drive and printer. The systems works [illegible] but I was supplied with [illegible] problem with [illegible] discs. At the end of mine has told me that normal discs will not work with double sided drives. Could someone tell me exactly what sort of disc I should buy as the price [illegible] with the different [illegible]

Ken Knox
Fair Oak
Eastleigh Hants

THE official discs you should buy are double sided double density 96tpi discs. These don't usually come cheap and in practice all floppy discs are manufactured by exactly the same process so you can get away with using normal single sided double density 48tpi discs so long as you use a well known brand such as Memorex or Dysan.

Zilch

MY DRAGON has recently stopped working when the screen just goes green with a cursor. Why does it do this, is it that the adaptor is too close to the computer?

Benedict O Reilly
St Annes
Redstone Hill
Redhill
Surrey

THE problem is unlikely to be caused by the position of your power supply. As you get a steady display the problem most likely lies in one of three areas: either the RAM, ROM or CPU is probably faulty.

The most common fault with Dragons of this type is with RAM chips. I suggest you contact one of the repair specialists who advertise in this magazine for a quotation, for instance Pan Electronics at Unit A10 Enterprise Centre Merthyr Industrial Park, Pentrebach, Merthyr, South Wales or one recommended locally by a knowledgeable friend.

Stylograph

I HAVE a CPA80 printer and am trying to use Stylograph but I have two problems. Firstly how can I change the character codes of Stylograph such as underlining to match those of my printer and secondly how can I stop Stylograph from sending a line feed at the end of each line. I've tried typing XMODE /P /F but it doesn't work.

Lothar Pilz
71 Woodville Road
Mooroolbark
Victoria
Australia

STYLOGRAPH can easily be modified to work with any printer codes simply by selling up a suitable style file. I've explained how to do this previously so I won't go into it again here but see the Stylograph manual for details.

On your second problem unfortunately Stylograph does not take any notice of the XMODE setting for line feed and there is no simple solution that I know of. If anyone has patched Stylograph to stop it sending a LF then please let us all know!

One fudge is to 'spool' your text to a file and then print this out from OS-9 rather than from within Stylograph.

HERE S MY CLASSIFIED AD
(Please write your copy in capitals on the lines below)

Name .....
Address .....
..... Tele .....

Please cut out and send this form to Classified Department Dragon User 12 —13 Little Newport St London WC2H 7PP

DRAGON 62 disc drive Dragon DOS joysticks games utilities telewriter rainbow writer DRS editor/assembler flex OS9 £250 (0278) 787478

DRAGON 32 drive printer lightpen tv software books £250 01 354 1296 eves/wkds

DRAGON 64 Dragon 32 cumana V2 0 DOS printer NLQ 12 disks data recorder word processor 40 cassettes full documentation magazines boxed £500 Telephone (0533) 28501

PRESTOSOFT compilation 1 five + programs including wiggler a multi-screen arcade game only £2 75 (0772) 774485

DRAGON 32 disk drive joysticks some games £130 ono workingham (0734) 784673.

YOUR basic programs printed for £1 50 send your tape and remittance to martin 9 Gray Cresent Plymouth Devon PL51DA

COMPLETE DRAGON 64 SYSTEM Single disk drive commer printer FLEX OS with Dynacalc spreadsheet dynacasl compiler and many utilities also disk based business accounts and mailer programes stop need larger computer only £179 o n o AP Johnson Pollers Bar (0707) 52686 work 52834 home

DRAGON 32 boxed 4 joysticks cover 45 games books magazines incl 8 months subs to Dragon user £99 ono Tel Kidlington (Oxon) 08675 78421

PRINTER BROTHER M 1009 for Dragon as new with manual £95 phone 01995 7145 evenings

LISTINGS SERVICE for Dragon users £1 for two print touts Vince Gledhill 3 Belgrave Gardens Ashington Northumberland NE 639SW

DISK drive with Dargon DOS complete with manual and telewriter word processor disk £100 tel 0225 708969 after 6pm

DRAGON LISTINGS printed Send program cassell and s a e to Diastar Sherwood House 42 Berron Road Burnham on Sea Somersel TA8 2EX Please include cheque or p/o for £0 75 per program made payable to Diastar

DRAGON 32 (boxed) with cassette recorder joysticks books user magazine and games tapes £75 Wimborne Dorsel (0202) 883814

SUPER DRAGON writer II excellent word processor cartridge used only once complete with tutorial £30 O N O Paul Thomas 144 Maesglas Llan Oovery Oyfed SA20 OOW

DRAGON SPARES — most available SAE for list including Transformers 74LS783 £10 25 6809E £3 25 6847 £2 50 2764 £2 10 CPU Boards 32K £22 Nick Spiers 114 Greenway Tunbridge Wells Kent TN2 3JN

UNTESTED Complete cased dragons 32K £38 64K Untested (Could be working!) All inc p/p Phone Nick 0892 44070

SOFTWARE!! forty one original games plus two joysticks — back issues of Dragon User and several books all for £60

DRAGON 32 boxed leads Dragon DOS drive seikosha GP500A printer lanfold paper recorder 20 games D/User mags books joystick telewriter elite calc filmaster rainbow writer spite magic edit + as New Benefleet Essex 0268 756431 £250 o n o

DRAGON 32 upgraded to 64K 3 joysticks 53 games light pen books mags cassette recorder £110 Delta DOS disk interface £40 0480 51421 after 6pm

JOYSTICKS

For Dragon Tandy [illegible] Joysticks easier to handle and last longer than others costing twice as much £5 95 each £10 95 the pair Inc Cheques and POs to **Penlren Dept CU 21 Woodhouse Road London N12 9EN**

PRINTER TEXAS 810 3 to 15 tractor Hr-Sased listing etc stand Dragon cable manual paper also RS232 £100 or swap for min A4 width printer with graphes Graham Trowbridge 60552 (wilts)

WANTED OS9 Editor/Assembler preferably with manual 0203 504842

STOP PLAYING GAMES

Use yo[illegible] make money [illegible] cu hobby [illegible] based [illegible] and part time [illegible] home [illegible] prospects Ope[illegible] game [illegible]

Westlink Promotions

Out on the tiles

***Gordon Lee** sets 'em up in time for Christmas*

FOLLOWING the ususal practice of including a mind bending game in the Christmas edition of Dragon User here is a colourful but tricky puzzle to exercise your brain! For the original on which this computer version is based I am indebted to *Games and Puzzles for Addicts* by Roger Millington

The game is played with sixteen coloured tiles — three tiles each of green yellow red and cyan and four orange tiles The object of the game is to place these tiles one at a time onto a coloured 4 by 4 grid The grid can be filled in any sequence and the coloured tiles can be placed in any order subject to the following rules

i) A tile cannot be placed on a square of its own colour

ii) A tile cannot be next to a square of its own colour either side by side or diagonally

iii) Only one tile may be placed on each square of the grid

Note that only the top (exposed) colour is counted so for example although a red tile cannot be placed next to a red square on the grid if the square is covered by say a green tile it might then be possible to place the red tile

If the program listing is run the computer will draw the initial layout of the grid The sixteen tiles are shown (reduced in size) on the right of the screen A tile is placed by moving the two arrows to locate the square to be played on and then pressing the initial letter of the colour of the tile to be played The arrow up key moves the arrow up cursor and the arrow left key moves the arrow left cursor

Once a move is made the computer checks that it is a valid move and if so places a tile Note that the grid has a black square showing in the centre of each compartment to indicate that it is uncovered Once a tile has been played this square disappears so you can tell where the tiles have been placed To place all sixteen tiles correctly and hence cover the grid requires a bit of ingenuity so have some fun! If you get stuck and wish to start again press O to quit Once you have solved the puzzle on the grid shown you can also try to solve it using a randomly generated grid by pressing R at the beginning of the game However when using this feature it cannot be guaranteed that a winning series of moves will be possible

Our competition this month also has a seasonal flavour Take the ten digits zero to ten and allocate one digit to each of the following letters

A F H M N O R S T and W

This should be done so that the following numbers as indicated by their letter substitutions have the required properties

SANTA is a prime number
FROST is a multiple of 7
NORTH is a multiple of 11
SNOWMAN is a perfect square

Merry Christmas



Prize

Those of you who can unravel the mysterious words of Gordon Lee this month will be contending for one of 20 copies of the new game from Smithson Computing 100 Screen Frankie Flee from Doctor Van Load and his evil sidekick Egor shoot bats bolts feet Feet?

Rules

First you slave for hours over a red hot Dragon Then you pack your solution a listing of the program you have created to find that solution (no cassettes please) the benefit of your ancient wisdom in the form of a tie breaker and your name and address into a modest envelope marked DECEMBER COMPETITION and tramp out across the deep crisp and even snow to post it to us here

The tiebreaker? Complete the line I want to be perfectly frank and if we like it we might send you a Frankie — even if you don't live in Hollywood

September winners

The winners of a £300 discount voucher from John Penn Software in the September competition are Fred Williers of Yarnfield E Anderson of Telford Terry Smith of Worcester H Grandy of Sheffield E Newman of Addlestone S Siddiqui of Chiswick T Fawcett of Hendon Simon Aubrey of Swindon D Davies of Bristol P Kirk of Aberdeen Frank Appleby of Aberystwyth J Boddy of Mill Hill Geoff Reed of Maidstone Jonathan Harrap of Wantage C Hitchinson of Middlesborough Phil Sapiro of Liverpool D Gray of Middlesborough Robin Telkman of Sale A Thomas of Staplehurst and A Henderson of Bromsgrove

Favourite tiebreaker comes from Mr Thomas who states baldly

Oh little flower upon the ground
I wish you were instead one pound
I couldn't have put it better myself

Solution

There are two sets of numbers 13651919 1365919 136591 13659 139 and 5530341,5308341 530341 50341 50415 41

JOHN PENN
DISCOUNT STORE FOR THE DRAGON

*** A HAPPY CHISTMAS TO ALL OUR CUSTOMERS ***

GAMES

[illegible] H ASK ADV Asc)	£3.00
[illegible] ADV (Cow	£5.00
RNC OF DARKNESS (Wilersoft)	£2.00
GOBDON BENNETT (Smithson)	£4.50
HARE RA SE@ DOUBLE PACK (Ha eso t search for he Golden Hare)	£4.00
BEST OF PCW (Centurion)	£5.00
SUNKEN C TY ADV (Silk)	£4.00
Bt OCKBUSTER QUIZ (Computerware	£4.50
SHOW JUMP (Computerwe e)	£5.50
T ME AT ACK T ido Wil ams)	£5.50
FRED CTO@ Me ey	£4.00
BEANSTALKER (Mic ov sion	£7.95
TIM LOVES CR CKET Peaksoft)	£4.00
SAS (Peaksoft	£2.00
PHOTO F N SH Peaksoft)	£2.00
BACK T@ACK tncent ve	£3.50
ET SET W LLY (Software P o ec s)	£5.00
MAN C M NER (Software P ojects)	£3.00
O HE LLO Oasis	£3.00
INVADER T CURE Oass s	£3.00
DY LANOES Oass s	£3.00

AND

CHESS ca t (Dragon Da a)	£10.00

CASTLEDGES

£4.00 each

RA t @UNNE@
CHOST ATTACK
LOSM C INVADERS
ASTROBLAST
METEOROIDS
CAVE HUNTE@

PERIPHERALS

CUMANA DISC	RRP	OUR PRICE
40 rack s ng e s ded	£149.95	£113.10
80 ack doub e s ded	£179.95	£107.30
240 ack sing e s ded	£269.95	£240.25
280 ack doub e s ded	399.95	£356.15
ce CumanaDisc	£75.50	£71.16

Ou p ce nc udes VAT and ca ago
SAM ch ps (7LS 783) ion Cumana @ ducts on yf £15.00
2 d hand re usable S opply discs £0.00 each or 10 or £4.00

EDUCATIONAL CORNER

D A Sec	£2.00 each n w to £3.00
S u M	
C c s Adv n u	
Typing tuto	£4.00

Dragon Educational series

Let s Count	
Shape Up	£2.00 each n w to £3.00
Number Chase	
Facemake	

Shards/Cambrian series

Fun to Learn	
Fam y Programs	£1.50 each o th ee for £3.00
Monste Maths	
Qu z Pack	
nfan Pack	
Snow Queen	
Ampa soft Cheshire Cat se ies	
M h s Leve (4 6)	
M h s Level (6-7)	
O ce e Maths	
Superspy	£3.50 each o two for £6.00
Bas c Tu or Beg nne s Level	
Bas Tu Advanced Leve	

UTILITIES/BUSINESS SOFTWARE

OS9 Sotwa e fo u (Ug m d ve a d D agon 64		
DYNACALC		
G M S		£21.00
BASIC 09		£20.00
C COMPILE@		£21.00
PASCAL		£27.00
STOCK @ECOD NG SYSTEM		£10.00
CHASH BOOK & VAT		£10.00

Harna Micro Software

BAS C 42		£14.95 (Mo u e a C S o y
+ with HELP ut ty		£19.95
with SPOOL vility		£18.95 n D agu Dos
w h HELP and SPOOL		£24.95
Har CumanaDos add £5.00 o above prices)		
Sourcemake (Parncomms)		£8.00
Spr e Mag c (Knight)		£5.00
G aph cs System (Sa amander)		£5.00
H Res Tex cartw ight		£3.00
Dream Ed ge/Assemble (D agon Data)		£5.00
Pe sona F nance (D Data)		£5.00
G aph c An mato (Dr Data)		£5.00
U ities (H Hen)		£5.00
D sassemb er (H ton)		£5.00
Persona Bank ng System (H ton)		£8.95
Shaper (Shards)		£3.00
E ect on c Autho wo d p ocessor (Smithson)	cass. £12.95	d sc £19.95

MST Business Software

Stock Con rol	cass £3.00	disc £4.00
Ma le/Address Book	cass £3.00	d sc £4.00

BARGAIN BASEMENT

£1.50 each five fo **£6.00** ten fo **£10.00**
P ease g ve at east two a te nat ves hen ode ng ve o mo e p og am

CHOCOLATE
DRAGON SELECT ONS
FLIPPER
ULT MATE ADVENTURE
KATERPILLAR ATTACK
UP PER SCOPE
MINED OUT
NORTH SEA O L
AMAZING
DETECT VE
HOME BASE
MYSTERY OF THE JAVASTAR
UXB
CHAMPIONS
SUPERSPY
AL EN ODYSSEY
C TY DEFENCE
@ RD RUNNE@
STALAG@ENO
N GHT FL GH
DONT PAN C
OSS E
@OPSW ZZLE
@C B LL
DEMON KN GHT
PICTURE PAZZ E
CELLS & SERPENTS
DRAGON TREK
PEDRO
DRAG @UNNE@
SU@PRISE
STOCKMA@KET
MOVIE PRODUCER
PETT GREW S
TRANSYLVANIAN TOWER
MIN GAMES
LEGGITT

HOW TO ORDER

J n nh m n ha Access orde quot ng the tles pub she price and tmed un v ve n A d ke Please nc ude 50 p fo postage/pack ng ng s ng e t ed Pos age to Europe s £2.00 and £4.00 fo es o w o P n would ke you ordo o be sent by a mat

J ephone numbe as we as you name and u addres

Ch u po n m payable o John Penn D scount Sotwa e A he so a e a d n phe a a an y

k houd we y o despatch t c oe s w t d

7h3

J. PENN
DISCOUNT SOFTWARE
Dean Farm Cottage, Kingsley, Bordon, Hants GU35 9NG
Tel Bordon (04203) 5970

TURBOCHARGE YOUR DRAGON:

With our great value hardware and software

DISK DRIVES

CUMANA 40 track drives
EXCL CARTRIDGE

SINGLE (180k)	£134 95
DUAL 6360k)	£249 95

CARTRIDGES FOR ABOVE

CUMANA DOS 2 0	£65 00
Delivery (mainland Britain)	£5 00

SOFTWARE FOR DRAGON 32/64/128 AND DRAGONDOS/CUMANA DOS 2 0

Professionally written programs for home, clubs, and small business, with random access disk filing and our 42 by 24 screen with true lower case

MONEYBOX **Personal accounts** **£14 99**
Controls income and expenses for bank account credit card etc Forecasting budgeting Optional VAT analysis for use as small business cashbook

MAILBOX **Mailing list** **£16 99**
Stores names addresses and up to 10 user defined fields Selects records by multiple tests Prints labels letter starts prints or displays reports

Sharebox **Stocks and shares** **£16 99**
Prints or displays share valuations capital gains dividends and tax credits income forecast price changes draws graphs of price trends

SALESBOX **Sales Ledger** **£19 99**
Balance brought forward with 4 debt periods Can print statements aged debt analysis daybooks labels nominal code report Can link to CASHBOX

BILLSBOX **Purchase Ledger** **£19 99**
Balance brought forward with 4 debt periods Can print remittance notes aged credit list labels daybooks nominal code report Can link to CASHBOX

CASHBOX **Nominal Ledger** **£19 99**
Double entry system posting debits/credits to up to 999 accounts Prints trial balance balance sheet profit and loss budgets forecasts audit trial Can read SALESBOX/BILLSBOX files

STOCKBOX **Stock control** **£19 99**
Records sales orders deliveries Prints low stock list orders due valuation turnover price list stock movements Can bulk change prices

ORDERBOX **Invoicing** **£16 99**
Prints invoices etc on plain or pre-printed paper Can link to SALESBOX or STOCKBOX

BASIC 42

An extended BASIC for the Dragon 64

Run your Dragon in 64K mode, while retaining BASIC and DOS. Print on the hi-res screen, using all the standard PRINT commands and a screen layout of 42 rows by 24 columns. Other features include

* Full upper/lower case/graphics character set
* REDEFINABLE characters
* Alternative character sets
* Control key for special characters
* REPEATING keys
* Commands in LOWER CASE (even filenames)
* 8 user defined independent WINDOWS
* 1 fixed non-destructive window
* CATCH command for automatic return to window
* INVERTED VIDEO (green on black/black on green)
* True UNDERLINING
* Extra PRINT commands and functions
* ROW and COLUMN commands for easier printing
* LIBRARY lists commands and functions
* Automatic startup of BASIC program
* TEXT command for software compatibility
* Takes NO memory from BASIC
* Patches for Dragondos 1 0
* Can load in extra UTILITIES from disk

HELP UTILITY
Extensions to BASIC 42 includes

* Change CURSOR character
* SCROLL disable
* PAUSE single step listing
* Enable/disable repeating keys
* Enable/disable BREAK key
* Improved TRON (including single stepping)
* Detailed HELP messages
* Expanded ERROR messages

SPOOL UTILITY
Use computer while printing

* 3 5K print buffer
* TYPIST program turns Dragon into typewriter

MORE TO COME: you ain t seen nothing yet

PRICES: Dragondos disk (Please state version)

BASIC 42	£14 95
HELP Utility	£5 00
SPOOL Utility	£5 00
Modification for CUMANA DOS	£5 00

Cheques/p o,s/Further details/dealer enquiries to:

HARRIS MICRO SOFTWARE

49 Alexandra Road, Hounslow, Middlesex, Tw3 4HP
Tel: (01) 570 8335

LR

FIRE FORCE

The Greatest Hi-Res Graphic Arcade Game Ever Written for Your Dragon/Tandy Colour 32K

IS HERE

PHASE 1 : *LEAD COMMANDO'S IN !!!*

PHASE 2 . *FLY PLANE OUT !!!*

The year is 1996. The only prototype of the IMFTC X18 'SPIRIT' low level attack plane has been forced down deep in Africa by a foreign power, who are holding it for ransom.
YOUR job is to lead a crack COMMANDO assault team (FIRE FORCE) and penetrate the enemy defences and fly this awesome combat vehicle back home.

£9.95

SHAOLIN MASTER ÷ plus ÷

Probably the BEST KUNG FU game on the Dragon/Tandy

WE THINK THESE PICTURES SAY IT ALL ! ! !

Challenge your family and friends to a contest of general knowledge, mental agility and spelling ability.
There are over 4000 clues, which should keep you busy for hours.

FOR 1 OR MORE PLAYERS

DUPLIDISK 2

The tape to disk copier you've all been waiting for. If you thought that DUPLIDISK 1 was good, this one is even BETTER. Not only will it transfer even MORE but it is compatable with: – DELTA, DRAGON D.O.S. 2.0 & 4.0, and CUMARNA D.O.S.

ORDER FORM

- ☐ DUPLICAS 5 ..... £8.45
- ☐ DICKIE SPACEMAN £6.45
- ☐ 6809 EXPRESS £6.45
- ☐ TERROR CASTLE £6.45
- ☐ SHRUNKEN SCIENTIST £6.45
- ☐ FIRE FORCE £9.95
- ☐ SHAOLIN MASTER PLUS £8.45
- ☐ TRIVIAL CROSSWORDS £6.45
- ☐ DUPLIDISK 2 ..... £8.45
- ☐ WEIRDS OF KESH £6.45
- ☐ DICKIE'S DEN £6.45

Please rush me the items I've ticked

I enclose a cheque for £ _____

Name _____

Address _____

_____ Post Code _____

Make cheques and P/O's payable to:

QUICKBEAM SOFTWARE

Post to

67 old nazeing road
broxbourne
herts EN10 6RN